

**NORTH SUMTER COUNTY UTILITY
DEPENDENT DISTRICT
POTABLE WATER SYSTEMS**

**CROSS-CONNECTION
CONTROL HANDBOOK**

REVISED DECEMBER 11, 2019

**OWNER
NORTH SUMTER COUNTY UTILITY DEPENDENT DISTRICT
984 OLD MILL RUN
THE VILLAGES, FL 32162
(352)750-0000**

**PREPARED BY:
ARNETT ENVIRONMENTAL, LLC
1038 LAKE SUMTER LANDING
THE VILLAGES, FL 32162
352-753-4747**

**NORTH SUMTER COUNTY UTILITY DEPENDENT DISTRICT
CROSS-CONNECTION CONTROL HANDBOOK
DECEMBER 2019**

STATEMENT OF POLICY AND LEGAL AUTHORITY	3
A. RULES CONCERNING THE PROTECTION OF THE POTABLE WATER SUPPLY SYSTEMS.....	5
B. EXCERPTS FROM STATE CODES AND REGULATIONS	6
C. RESULT OF NON-COMPLIANCE WITH HANDBOOK	7
D. HAZARD REVIEW PROCESS AND BFP ASSEMBLY DETERMINATION.....	7
E. INSPECTION.....	10
F. EXISTING FACILITIES	10
G. NEW FACILITIES	11
H. TESTING AND REPORTING	11
I. REPAIRS	11
J. EDUCATION PROGRAM	12
K. COMPLIANTS AND EMERGENCIES	12
L. RECORDKEEPING	13
M. EFFLUENT REUSE	13
N. DEFINITIONS	18
APPENDIX A LETTERS AND FORMS	22
CROSS-CONNECTION CONTROL PROGRAM LETTER TO COMMERCIAL CUSTOMER	23
NSCUDD WATER SYSTEMS CROSS-CONNECTION CONTROL SURVEY FORM	26
NSCUDD POTABLE WATER SYSTEMS BACKFLOW PREVENTION ASSEMBLY INSTALLATION RECORD	28
APPENDIX B APPROVED BACKFLOW PREVENTION ASSEMBLIES & INSTALLATION DETAILS	30
DOUBLE CHECK VALVE ASSEMBLY.....	31
REDUCED PRESSURE ASSEMBLY	42
INSTALLATION DETAILS	55

STATEMENT OF POLICY AND LEGAL AUTHORITY

Under the provisions of the Safe Drinking Water Act adopted by the E.P.A. in 1974, the potable Water Purveyor (supplier) is held responsible for compliance to the provisions of the Act, to include a warranty that water quality provided by his operation is in conformance with the E.P.A. standards at the source, and is delivered to the Customer without the quality being compromised as a result of its delivery through the distribution system.

The safe and efficient operation and maintenance of backflow assemblies is essential in order to properly protect the public from possible hazards caused by contamination. To this end, North Sumter County Utility Dependent District Company (NSCUDD) endorses the Statement of Policy adopted by the American Water Works Association (AWWA) as follows:

"The American Water Works Association recognizes that the Water Purveyor has a responsibility to provide its Customers at the service connection with potable water that is safe under all foreseeable circumstances. Thus, in the exercise of this responsibility, the Water Purveyor must take reasonable precautions to protect the community distribution system from the hazards originating on the premises of its Customers that may degrade the water in the community distribution system.

Cross-connection control and plumbing inspections on premises of water Customers are regulatory in nature and should be handled through the rules, regulations and recommendations of the health authority or the plumbing-code enforcement agencies having jurisdiction. The Water Purveyor, however, should be aware of any situation requiring inspection and/or re-inspection necessary to detect hazardous conditions resulting from cross-connections. If, in the opinion of the Utility, effective measures consistent with the degree of hazard have not been taken by the regulatory agency, the Water Purveyor should take such measures as he may deem necessary to ensure that the community potable water distribution system is protected from contamination. Such action would include the installation of a backflow prevention assembly, consistent with the degree of hazard at the service connection or discontinuance of the service.

In addition, Customer use of potable water from the community distribution system for cooling or other purposes within the Customer's system and later return of the water to the community distribution system is not acceptable and is opposed by AWWA."

NSCUDD has adopted this Cross-Connection Control Handbook through adoption of Chapter I of the Rules of the NSCUDD. Legal authority for adoption of these Rules is provided via 189.423. F.S. These Rules took effect on October 26, 2010.

In order to implement an effective cross-connection control program, NSCUDD adopts the following guidelines:

1. Establish a Cross-Connection Control Handbook outlining policies, rules, regulations, and procedures to be followed to insure the quality of water supplied by the potable water supply systems.
2. Implement an Education Program which may include information provided at the time of request for service, mail-outs to Customers, and newspaper articles.

3. Send personnel who monitor compliance with the program to courses on backflow prevention (BFP) and cross-connection control.
4. Conduct periodic meetings with local plumbing inspection personnel, licensed plumbers and others who will be involved in the installation, inspection, testing and repair of backflow prevention assemblies.
5. Instruct meter readers and maintenance personnel to watch for cross-connections during their daily work schedules and report any cross-connections to management.
6. Establish a policy that specifies the types of service connections that will require a backflow prevention assembly, proper location of the backflow prevention assembly, and a list of all approved assemblies.
7. Ensure that any new construction is reviewed to assess the degree of hazard and ensure that the proper backflow prevention assembly is installed.
8. Continue a backflow protection program to install a residential dual check backflow device at the potable water service to every new residence (existing residential dual check backflow devices are replaced at a minimum of once every ten years).
9. As existing water meters are repaired or replaced at residences, ensure that a residential dual check backflow preventer is set with the new or reworked water meter.
10. Prepare a listing of all testable backflow assemblies in the system and ensure that they are tested by certified test personnel on an annual basis.
11. Maintain records associated with installation, testing, and repair of backflow prevention assemblies.
12. Provide a customer service contact number and specify information handling procedures for complaints and emergencies related to backflow prevention assemblies and possible cross contamination.

The Cross Connection Control Program Handbook may be amended at any time at the discretion and approval of the District Manager.

A. RULES CONCERNING THE PROTECTION OF THE POTABLE WATER SUPPLY SYSTEMS

In order to protect the public water supply systems from contamination due to cross-connections, NSCUDD hereby establishes the following rules:

- A.1. No installation of potable water supply piping or part thereof shall be made in such a manner that it will be possible for used, unclean, polluted or contaminated water, mixtures or substances to enter any portion of such piping from any tank, receptacle, equipment or plumbing fixture by reason of back-siphonage, back-pressure, or any other cause either during normal use and operation thereof or when any such tank, receptacle, equipment or plumbing fixture is flooded or subject to pressure in excess of the pressure in the hot or cold water piping.
- A.2. No person shall make a connection or allow one to exist between pipes or conduits carrying domestic water supplied by any public or private water service system, and any pipes, conduits or fixtures containing or carrying water from any other source or containing or carrying water which has been used for any purpose whatsoever, or any substances whatsoever, unless there has been provided an approved backflow prevention assembly. The approval of NSCUDD must be obtained before any connection is made between the domestic supply and any auxiliary water system.
- A.3. No plumbing fixture or device shall be installed or maintained or shall be connected to any domestic potable water supply when such installation or connection may provide a cross-connection between a distributing system of water for drinking and domestic purposes and water which may become contaminated by such plumbing fixture or device unless there has been provided an approved backflow prevention assembly.
- A.4. No water piping supplied by any private water supply system or industrial piping system shall be connected to the potable water system without approval from the NSCUDD.
- A.5. Any business, resident, or any other connection having been found by NSCUDD to be a potential backflow source or which meets the established requirements for backflow prevention protection shall install or cause to be installed an approved backflow prevention assembly.
- A.6. All assemblies, which consist of independent units assembled for the purpose of preventing backflow, shall comply with the material, operational, and other specifications of The American Water Works Association (AWWA), The American Society of Sanitary Engineering (ASSE), or the Foundation for Cross-Connection Control and Hydraulic Research (FCCCHR) as required for backflow prevention assemblies. In order to ensure proper operation, all assemblies shall be completely assembled by the manufacturer with all required components. Resilient seated shut-off valves and test cocks are considered to be an integral part of the assembly.

- A.7. The assembled piping shall be thoroughly flushed before installing the backflow prevention assemblies.
- A.8. All backflow prevention assemblies shall be adequately supported.
- A.9. All backflow prevention assemblies are the property of the customer. NSCUDD shall have no ownership or responsibility for the proper installation, operation, maintenance, or repair of any backflow prevention assembly.

B. EXCERPTS FROM STATE CODES AND REGULATIONS

The following excerpts are herein incorporated into this program by reference, including any future amendments. In the event of any conflict between this Document and other Codes or Regulations, excluding State and Federal Laws, the terms and provisions of this Document shall prevail.

B.1. RULES OF THE STATE OF FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION

SECTION 62-550.200(26):

(26) "CROSS-CONNECTION" means any physical arrangement whereby a public water supply is connected, directly or indirectly, with any other water supply system, sewer, drain, conduit, pool, storage reservoir, plumbing fixture, or other device which contains or may contain contaminated water, sewage or other waste, or liquid of unknown or unsafe quality which may be capable of imparting contamination to the public water supply as the result of backflow. By-pass arrangements, jumper connections, removable sections, swivel or changeable devices, and other temporary or permanent devices through which or because of which backflow could occur are considered to be cross-connections.

SECTION 62-555.360(1), (2) AND (3):

(1) Cross-connections, as defined in Rule 62-550.200, F.A.C. are prohibited unless appropriate backflow protection is provided to prevent backflow through the cross-connection into the public water system. This does not prohibit a public water system from being interconnected to another public water system of the same type without backflow protection.

(2) Each community water system (CWS) shall establish and implement a cross-connection control program utilizing backflow protection at or for service connections from the CWS in order to protect the CWS from contamination caused by cross-connections on customers' premises.

(3) Upon discovery of a prohibited or inappropriately protected cross-connection, public water systems either shall ensure that the cross-connection is eliminated shall ensure that appropriate backflow protection is installed to prevent backflow into the public water system, or shall discontinue water service.

B.2. FLORIDA BUILDING CODE, PLUMBING

CHAPTER 6 – WATER SUPPLY AND DISTRIBUTION:

Section 608 – Protection of Potable Water Supply (Section in its entirety)

608.1 General. A potable water supply system shall be designed, installed and maintained in such a manner so as to prevent contamination from nonpotable liquids, solids or gases being introduced into the potable water supply through cross-connections or any other piping connections to the system. Backflow preventer applications shall conform to Table 608.1 , except as specifically stated in Sections 608.2 through 608.16.10.

C. **RESULT OF NON-COMPLIANCE WITH HANDBOOK**

Any person or customer failing to comply with this program or part hereof shall be deemed to be in non-compliance, and potable water service may be terminated by NSCUDD until corrective actions required by this program are completed and verified.

C.1. FEES DISCONNECT/RECONNECT:

Fees may be assessed to customers regarding actions taken by NSCUDD associated with disconnection/reconnection of service, performance of backflow prevention assembly testing and/or repair, or any other applicable actions.

Any person, persons, or customers having been deemed to be in non-compliance with this program shall pay fees as set by NSCUDD.

C.2. TERMINATION OF SERVICE:

In emergency conditions, when the public potable water supply is being contaminated or is in danger of contamination, water service may be disconnected by NSCUDD.

D. **HAZARD REVIEW PROCESS AND BFP ASSEMBLY DETERMINATION**

D.1. All commercial facilities that intend to connect to a NSCUDD potable water system shall submit a Cross-Connection Control Survey Form at the time of application for water service (see Appendix A).

Failure to comply with the submittal of the Cross-Connection Control Survey Form shall be a violation of this program. Upon review, NSCUDD shall evaluate the hazard potential and determine the type of backflow prevention assembly that is required. There are varying degrees of hazard, and the degree of protection shall be commensurate with the degree of hazard.

D.2. All commercial connections to a NSCUDD potable water system shall be required to have a backflow prevention assembly as otherwise specified herein.

Commencing with the approval of this Handbook by NSCUDD, all backflow prevention assemblies that are installed shall be approved by NSCUDD or its designated representative.

- D.3. **Residential** - All new residential potable water connections will include a residential dual check backflow prevention device that is integral to the meter. As all existing residential potable water meters are repaired or replaced, water system operations personnel will ensure that a residential dual check backflow prevention device is present or installed. Whenever a residential potable water meter is replaced, the dual check device will be replaced or rebuilt as well.

If any devices or equipment are installed that connect to a residential potable water line that have the potential for increasing the level of hazard to the public water systems, the resident will be responsible for installing an additional backflow prevention assembly in compliance with the requirements of 62-555 F.A.C. and this Handbook. All assemblies shall be installed in accordance with the manufacturer's recommendations. Added backflow prevention assemblies shall be required to be tested and reported in accordance with the requirements of Section H of this Handbook.

If the provisions of this Handbook are not met, NSCUDD may disconnect the potable water service until such time as proper corrections are made and verified.

Home dialysis machines or any other equipment or device that presents a high hazard to the potable water system shall require the installation of a reduced pressure assembly. The assembly shall be installed next to the home, upstream of any other connection.

- D.4. **Assembly Location** - Backflow prevention assemblies shall be located on the facility side of the potable water meter, upstream of any connection points to the water service line. Reduced pressure assemblies shall be located a minimum of 12 inches above finished grade as close to the building as possible so as to allow for screening by landscaping. In no case shall there be any connections to the potable water service upstream of the backflow prevention assembly.
- D.5. **Assembly Type** - Backflow prevention assembly types shall be as determined by NSCUDD or its designated representative. The following chart shows, in general, the types of assemblies that are required as a minimum level of protection for various types of commercial connections. Final determination of the assembly type will be made by NSCUDD or its designed representative and will be based on the assessment of the potential hazard to the potable water system.

NSCUDD COMMERCIAL CONNECTIONS APPROVED BACKFLOW PREVENTION ASSEMBLIES	
Connection Type	Approved BFP Assembly
Restaurant	DCVA
Medical/Dental/Veterinary/Eye Care	RP
Laboratory/Blood Center	RP
Office	DCVA
Grocery Store	RP
Beauty or Nail Salon/Spa	RP
Drug Store	DCVA
Pet Store	DCVA
Convenience Stores	DCVA
Banks/Financial	DCVA
Home Improvement/Hardware	RP
Clothing Retail	DCVA
Furniture Retail	DCVA
Restroom Facility	DCVA
Pool	DCVA with Air Gap
Postal Facility	DCVA
School	DCVA
Church	DCVA
Funeral Home	RP
Maintenance Facility (Golf, Landscape, etc.)	RP
Wastewater Pumping Station	RP
Wastewater Treatment Plant	RP
Commercial Car Wash	RP
Assisted Living/Nursing Facility	RP
Independent Living Facility	DCVA
Skilled Nursing Facility	RP
Commercial Laundries/Dry Cleaners	RP
Automotive Repair/Tire Store	RP
Photo Processing Facilities	RP
Pest Control Companies	RP
Cooling Towers	RP
Hospitals	RP
Definitions	
BFP	Backflow Prevention
DCVA	Double Check Valve Assembly
RP	Reduced Pressure Assembly
Notes	
1. Backflow Prevention Assemblies for facility types not described above shall be submitted to and approved by NSCUDD or its authorized representative prior to installation.	
2. An alternate Backflow Prevention Assembly may be submitted for approval. Alternate assemblies shall be approved by NSCUDD or its authorized representative prior to installation.	

- D.6. **Approved Assemblies** – Refer to Appendix B for general information on approved backflow prevention assemblies.

Final approval of the specific assembly (manufacturer and model) shall be by NSCUDD or their designated representative.

- D.7. Upon completion of the installation of a backflow prevention assembly, the Owner shall submit to NSCUDD detailed installation data on the Installation Record form provided in Appendix A.

E. INSPECTION

- E.1. Duly authorized employees or representatives of NSCUDD shall be permitted to enter upon properties for the purpose of sampling or testing the potable water supply, or to make inspections or observations of connections to the potable water supply. Refusal to allow inspection shall constitute a violation of this program.
- E.2. If a backflow prevention assembly is required, the Customer shall have installed the correct backflow prevention assembly as determined by NSCUDD. At such time, an inspection by NSCUDD may be performed; such inspection by NSCUDD shall determine satisfactory compliance by the Customer with this program. If such inspection fails to show compliance with this program, NSCUDD shall not be compelled to establish potable water service until such time that satisfactory compliance has been achieved.

F. EXISTING FACILITIES

- F.1. All premises where cross-connections are suspected shall be surveyed by NSCUDD to determine if a detailed inspection will be required. The Owners of the suspected premises shall be contacted to secure an appointment for inspection of the premises. The Owner or his authorized representative will be required to accompany the Inspector during the tour of the premises. A cross-connection survey form will be completed by the Inspector and signed by the Owner or his representative. The Owner shall be made aware of any corrective measures that need to be made. Upon conformance to the requirements in the notification, the Owner shall immediately notify NSCUDD to schedule a date for re-inspection.
- F.2. In order for potable water service to be continued, corrective measures identified by NSCUDD must be completed by the owner within sixty (60) days or an alternate timeframe as specified by NSCUDD.
- F.3. If corrective measures are not completed within the specified timeframe, NSCUDD may disconnect potable water service.
- F.4. If an existing condition is deemed an immediate hazard to a NSCUDD water system, NSCUDD may disconnect the potable water service until such time as corrective measures are completed and verified.

G. NEW FACILITIES

- G.1. All new commercial connections to a NSCUDD potable water system shall require a backflow prevention assembly in accordance with the provisions of this handbook.
- G.2. The installation of thermal expansion devices and/or pressure relief valves is needed within the closed-loop plumbing system created by the required use of backflow prevention assemblies to protect the NSCUDD water systems.

H. TESTING AND REPORTING

- H.1. Testing shall be required on all backflow prevention assemblies. Testing is to be performed by a certified Backflow Prevention Device Technician in accordance with AWWA standards or an individual holding the necessary license. All backflow prevention assemblies, and all assemblies installed where testing is made possible by the design of the assembly shall be tested a minimum of once every twelve (12) months. In the opinion of NSCUDD, if a backflow prevention assembly is used in high hazard applications, it may be required by NSCUDD to be tested more frequently.
- H.2. Annual backflow prevention assembly testing and any required maintenance or repair shall be completed and reported to NSCUDD by July 1st of each year. An alternate schedule or greater frequency may be approved/required by NSCUDD.
- H.3. Customers may receive a past due notice from NSCUDD if an annual passing test and report is not received in accordance with the dates indicated by NSCUDD.
- H.4. If an acceptable test report that includes all of the required information, as shown in Appendix A, titled "NSCUDD Potable Water System Backflow Prevention Assembly Test and Maintenance Report Requirements" is not received in accordance with the required timeframes, NSCUDD, at its option, may perform any required maintenance, repair, or installation, as applicable, and then have the test conducted. All costs incurred by NSCUDD, as provided for by Rule, will be included on the customer's utility bill.

I. REPAIRS

- I.1. A backflow prevention assembly that fails a test or does not meet the standards of this program shall be repaired/replaced by the Owner to correct any deficiencies or problems with the assembly. The Customer, Owner or Authorized Agent for the Owner shall be responsible for any and all repairs/replacement necessary to maintain good working condition of the backflow prevention assembly. Repairs shall be performed by a certified backflow prevention device repair technician or an individual holding the necessary licensing.

- I.2. Certified backflow prevention device repair technician or an individual holding the necessary license shall determine and affirm to NSCUDD satisfactory repair and compliance of the backflow prevention equipment. Said affirmation of compliance by the technician shall be provided to NSCUDD in accordance with the schedule in section H, Testing and Reporting.

J. EDUCATION PROGRAM

- J.1. Upon application for water service, all potential commercial customers will receive a copy of a letter titled “Cross-Connection Control Program.” This letter explains the responsibilities of NSCUDD and the commercial customer regarding our Cross- Connection Control Program. The letter also includes instructions for downloading a copy of the Cross Connection Control Handbook. A copy of the letter can be found in Appendix A.
- J.2. Commercial customers will receive an annual letter by mail prior to their backflow assembly test due date as a reminder of the reporting requirements and that their annual backflow assembly test is due. If an acceptable backflow assembly test report is not received within the specified time, a past due letter will be mailed to the customer advising them of their non-compliance. If after receiving a past due letter an acceptable backflow assembly test report is not received within the specified time, further steps will be taken by NSCUDD as explained in Section H Testing and Reporting. It is the responsibility of the customer to ensure that an acceptable backflow assembly test report is submitted for each backflow assembly that exists at their location.
- J.3. Periodic newspaper articles will be in the local newspaper to notify residential and commercial customers of the backflow prevention and water system protection issues.
- J.4. Meter readers and utility operations personnel will receive training regarding the requirements for commercial and residential backflow prevention assemblies. Locations that are found to be non-compliant with the provisions of this handbook will receive individual notification of actions that must be taken to bring the correction into compliance.

K. COMPLAINTS AND EMERGENCIES

- K.1. **Normal Business Hours-** Complaints and emergencies regarding backflow shall be directed to the NSCUDD utility customer service number (352) 750-0000 from 8:00AM to 5:00PM, Monday through Friday.
- K.2. **After Hours and on Weekends-** Complaints and emergencies regarding backflows shall be directed to Community Watch (352) 753-0550.
- K.3. Information regarding backflow complaints and emergencies will be relayed to utility operations personnel who will implement required response actions. Utility operations personnel are on call twenty-four (24) hours per day, seven day (7) days per week.

- K.4. In the event of an identified cross-connection or backflow occurrence the NSCUDD utility response procedures can be found in Appendix A.

L. RECORDKEEPING

- L.1. All records will be maintained for not less than ten (10) years.
- L.2. Records will be maintained by the NSCUDD Utility Department or their designated representative.
- L.3. Records will be kept on items including but not limited to:
- a) Cross-Connection Survey Forms
 - b) Backflow Prevention Assembly-Installation Records
 - c) Backflow Prevention Assembly-Test and Maintenance Reports
 - d) Backflow Compliant and Emergency Work Orders
 - e) Education Program Materials

M. EFFLUENT REUSE

- M.1. The NSCUDD Wastewater Treatment Plants (WWTP's) shall supply reclaimed water for the development's golf courses. The reclaimed water source consists of treated wastewater effluent, which satisfies requirements for slow-rate land application systems on public access areas in accordance with Chapter 62-610 F.A.C. NSCUDD shall have the responsibility of operating and maintaining the reclaimed water transmission/distribution system.
- M.2. At this time there is no plan to make reclaimed water available for residential or commercial use. If this were to occur in the future, all regulatory requirements would be complied with prior to initiating residential or commercial use of reclaimed water.
- M.3. In addition to the potable water utilities, NSCUDD also operates and maintains The Villages Water Conservation Authority (VWCA), which is a non-potable irrigation water system. This non-potable irrigation water system supplies and distributes non-potable water to satisfy the required irrigation and fire protection demands for the residential and commercial properties as well as the irrigation needs of the boulevard right-of-ways. The non-potable water source consists of storm water and ground water from a total of nine (9) lower Floridan Aquifer irrigation wells.
- M.4. **WASTE TREATMENT AND DISINFECTION-** Pre-application waste treatment shall result in reclaimed water that meets, at a minimum, secondary treatment and high-level disinfection. The reclaimed water shall not contain more than 5.0 milligrams per liter of suspended solids before the application of the disinfectant. Filtration shall be provided for TSS control. Chemical feed facilities for coagulant, coagulant aids, or polyelectrolytes shall be provided. Such chemical feed facilities may be idle if the TSS limitation is being achieved without chemical addition.

- M.5. **MONITORING AND OPERATING PROTOCOL-** Reclaimed water limitations shall be met after disinfection and before discharge to holding ponds or reuse systems. The total suspended solids limitation shall be achieved before disinfection, regardless of the actual reclaimed water compliance monitoring location.

The NSCUDD WWTP's shall include continuous on-line monitoring for turbidity before the application of the disinfectant. Continuous on-line monitoring of total chlorine residual shall be provided at the compliance monitoring point. Instruments for continuous on-line monitoring of turbidity and disinfectant residuals shall be equipped with an automated data logging or recording device.

Continuous on-line monitoring instruments shall be maintained according to the manufacturer's operation and maintenance instructions. Please refer to the Effluent Operating Protocol for the NSCUDD WWTP's for more detailed descriptions and instructions.

Reclaimed water produced at the NSCUDD WWTP's that fails to meet the criteria established in the operating protocol shall not be discharged into the system storage or reuse system. Such substandard reclaimed water (reject water) shall be either stored for subsequent additional treatment or shall be discharged to a permitted effluent disposal system (i.e. rapid infiltration basins).

- M.6. **PUBLIC NOTIFICATION AND ADVISORY SIGNS-** The public shall be notified of the use of reclaimed water. This shall be accomplished by posting the advisory signs designating the nature of the reuse project area where reuse is practiced, notes on scorecards, or by other methods. Examples of some of the notification methods, which may be used by permittees include, posting advisory signs at the entrance to a golf course. Advisory signs shall include the text, "Do not drink" in English and in Spanish together with the equivalent standard international symbols.

Advisory signs shall be posted adjacent to basins used to store reclaimed water that are not located at the domestic wastewater treatment facilities.

Advisory signs at storage basins shall include the text, "Do not drink" and "Do not swim" in English and Spanish together with the equivalent standard international symbols.

The NSCUDD shall ensure that users of reclaimed water and non-potable water are informed about the origin, nature and characteristics of reclaimed water and non-potable water; the manner in which reclaimed water and non-potable water can be safely used; and limitations on the use of reclaimed water and non-potable water.

Neither reclaimed water nor non-potable water shall be used to fill swimming pools, hot tubs, or wading pools.

M.7. COLOR-CODING AND LABELING OF RECLAIMED WATER LINES- All reclaimed water valves and outlets must be appropriately tagged and labeled as reuse in order to inform the public that the source is non-potable and to prevent the consumption of reclaimed water. Likewise, all non-potable water valves and outlets must be appropriately tagged and labeled as non-potable in order to inform the public that the source is non-potable and to prevent the consumption of non-potable water. Signs on these appurtenances shall bear the words, "Do not drink" in English and in Spanish together with the equivalent international symbol.

1. Reclaimed water valve boxes shall be adjustable with covers cast with the inscription RECLAIMED WATER in legible lettering on the top.
2. All reclaimed and non-potable water valves and outlets shall be installed in such a manner that restricts public access.
3. Vaults for reclaimed and non-potable water hose bibs and outlets shall be locked or require a special tool to operate the hose bib or outlets. All underground piping which is not manufactured of metal or concrete shall be color coded for reclaimed and non-potable water distribution systems using Pantone Purple 522C. Underground metal or concrete piping shall be color coded or marked using purple as the predominate color. If tape is used to mark the pipe, the tape shall be permanently affixed to the top and each side of the pipe. A single tape may be used along the top of the pipe for pipes less than 24 inches in diameter.
4. Installation shall be performed in accordance with applicable provisions of AWWA Manual M23 (PVC Pipe) and AWWA Standard C600 (Ductile Iron Pipe).

M.8. MINIMUM SEPARATION DISTANCES- Horizontal Separation: A minimum horizontal separation distance of 3 feet (measured outside to outside) between reclaimed water lines and potable water mains. The minimum horizontal separation distance between non-potable water lines and potable water mains is also 3 feet (measured outside to outside). Smaller horizontal separation distances are allowed provided one of the following conditions is met.

1. The top of either the reclaimed water main or the non-potable water main is installed at least 18 inches below the bottom of the potable water main.
2. The reclaimed water main or the non-potable water main is encased in concrete.
3. The applicant provides an affirmative demonstration in the engineering report that another alternative will result in an equivalent level of protection.

M.9. **VERTICAL SEPARATION-** Reclaimed water lines and non-potable water lines crossing under potable water mains shall be installed to provide a minimum vertical separation distance of 18 inches between the invert of the upper pipe and the crown of the lower pipe. Where the minimum vertical separation cannot be maintained one of the following conditions shall be met.

1. The crossing shall be arranged so that the reclaimed water pipe joints or non-potable water joints are equidistant from the point of crossing with no less than 10 feet between any two joints.
2. The reclaimed water main or the non-potable water main may be placed in a sleeve or encased in concrete to obtain the equivalent of the required 10 feet separation.

Where there is no alternative to reclaimed water pipes or non-potable water pipes crossing over a potable water main, the criteria for minimum separation between lines and joints listed above shall be required.

M.10. **SETBACK DISTANCE-** The reclaimed water system shall maintain the following setback distances.

1. Setback distance of 75 feet from the edge of the wetted area of the public access land application area to potable water supply wells that are either existing or are proposed which have been approved by FDEP or by the department of health.
2. Setback distance of 75 feet from reclaimed water transmission facility to a public water supply well.
3. Setback distance of 100 feet from reuse facilities to outdoor public eating, drinking and bathing facilities, low trajectory nozzles, or other means to reduce aerosol formation.
4. Setback distance of 100 feet from indoor aesthetic features, such as decorative pools or fountains, using reclaimed to adjacent indoor public eating and drinking facilities where the aesthetic features and eating and drinking facilities are within the same room or building.

Setback distances for potable water supply wells shall be applied only for new or expanded reuse facilities. Setback distances shall not be applied when considering renewal of a permit.

No setback distance is required for other potable water supply wells or to non-potable water supply wells. Setback distances are not required for surface waters or developed areas.

CROSS-CONNECTION INSPECTIONS- NSCUDD is responsible for conducting inspections within the reclaimed water service area and non-potable water service area to verify proper connections, monitor proper use of reclaimed water, and minimize the potential for cross-connections. Inspections are required when customers first connect to the reclaimed water distribution system.

M.11. IDENTIFICATION OF A CROSS-CONNECTION- The following procedures shall be initiated in the event that a cross-connection between a reclaimed water line or non-potable water line and a potable water line is discovered.

1. Potable water service to the affected area shall be immediately discontinued.
2. The cross-connection shall be eliminated.
3. Install a double check backflow prevention assembly at a potable water service connection point (to prevent contamination of the potable water system) and connect service to the potable water system affected area.
4. Flush the contaminated lines with potable water for a minimum of 30 minutes.
5. Inject sodium hypochlorite solution (5 mg/l- residual) at the backflow prevention assembly. The backflow prevention assembly shall be designed to have an injection port.
6. Service lines shall be filled with sodium hypochlorite solution until chlorine can be detected at all fixtures or at all connection points to the potable system.
7. A minimum 30-minute residence time shall be required.
8. A final flush of the lines shall be performed with potable water for a minimum of 30 minutes.
9. Perform two bacteriological and chlorine residual tests on two consecutive days to verify that service can be cleared. The backflow prevention assembly shall be removed only when the lines have been cleared for service.
10. The affected area shall be inspected for other possible cross-connections.
11. NSCUDD shall report any cross-connections within 24 hours of discovery to the appropriate FDEP district office and the drinking water program staff of the county health department.

12. NSCUDD shall submit a written report of any cross-connections to FDEP and the county health department within 5 days of its discovery. The report shall include the following details.
- A description of the cross-connection.
 - How the cross-connection was discovered.
 - The exact date and time the cross-connection was discovered.
 - The approximate time the cross-connection has existed.
 - The cause of the cross-connection (how it occurred).
 - The steps taken to correct the cross-connection.
 - Whether or not reclaimed water was consumed, and if so, whether any potential illness was reported.
 - Whether drinking water system was contaminated, and if so, the steps taken to clear the distribution lines.
 - When the cross-connection was corrected or is expected to be corrected.
 - Plan of action for subsequent testing for other possible cross-connections in the area.
 - Evaluation of the NSCUDD's cross-connection control and inspection program to ensure that future cross-connections do not occur.

N. DEFINITIONS

AIR GAP: A physical separation between the free-flowing discharge end of a potable water supply pipeline and an open or non-pressure receiving vessel. An "approved air-gap separation" shall be at least double the diameter of the supply pipe measured vertically above the top of the rim of the vessel. In no case shall it be less than 1 inch.

APPROVED: Accepted by NSCUDD.

AUXILIARY WATER SUPPLY: Any water supply on or available to the premises other than NSCUDD approved potable water supply. These auxiliary waters may include water from another purveyor's potable water supply or any natural source(s) such as a well, spring, stream, river, harbor, etc., or "used waters" or "industrial fluids."

BACK PRESSURE: Any elevation of pressure in the downstream piping system (by pump, elevation of piping, or steam and/or air pressure) above the supply pressure at the point of consideration, which would cause - or tend to cause - a reversal of the normal direction of flow through the backflow prevention assembly.

BACK-SIPHONAGE: A form of backflow due to a reduction in system pressure, which causes a negative or sub-atmospheric pressure to exist at a site in the water system.

BACKFLOW: The undesirable reversal of flow of water or mixtures of water and other liquids, gases or other substances into the distribution pipes of the potable supply of water from any source or sources.

BACKFLOW PREVENTION ASSEMBLY: A device or means designated to prevent back pressure, backsiphonage, or backflow.

CONTAMINATION: An impairment of the quality of the potable water by sewage, industrial fluids or waste liquids, compounds or other materials to a degree which creates an actual hazard to the public health through poisoning or through the spread of disease (see also pollution).

CROSS-CONNECTION: Any physical arrangement whereby a potable water supply is connected, directly or indirectly, with any other water supply system, sewer, drain, conduit, pool, storage reservoir, plumbing fixture, or other device which contains or may contain contaminated water, sewage, or other water or liquid of unknown or unsafe quality which may be capable of imparting contamination to the potable water supply as a result of backflow. Bypass arrangements, jumper connections, removable sections, swivel or changeable devices, and other temporary or permanent devices through which or because of which backflow could occur are considered to be cross-connections.

CROSS-CONNECTION, CONTROL BY CONTAINMENT: The installation of an approved backflow prevention assembly at the service connection to any Customer's premises where it is not physically and economically feasible to find and permanently eliminate or control all actual or potential cross-connections within the Customer's water system; or it shall mean the installation of an approved backflow prevention assembly on the service line leading to and supplying a portion of a Customer's water system where there are actual or potential cross-connections which cannot be effectively eliminated or controlled at the point of connection.

CROSS-CONNECTION, CONTROLLED: A connection between a potable water system and a non-potable water system with an approved backflow prevention assembly properly installed that will continuously afford protection against contamination or pollution commensurate with the degree of hazard.

DOUBLE CHECK VALVE ASSEMBLY: An assembly composed of two (2) single, independently acting check valves, including tightly closed shut-off valves located at each end of the assembly and suitable connections for testing the water tightness of each check valve.

A check valve is a valve that is drip-tight in the normal direction of flow when the inlet pressure is 1 psi and the outlet pressure is zero. The check valve shall permit no leakage in a direction reverse to the normal flow. The closure element (e.g., clapper) shall be internally weighted or otherwise internally loaded to promote rapid and positive closure.

DUAL CHECK VALVE ASSEMBLY: An assembly of two (2) spring loaded, independently operating check valves without tightly closing shut-off valves and test cocks, generally employed immediately downstream of the water meter to act as a containment device.

HAZARD, DEGREE OF: A measure of hazard derived from an evaluation of the potential risk to public health and the adverse effect of the hazard upon the potable water system.

HAZARD, HEALTH: Any condition, device or practice in the water supply system and its operation which could create or, in the judgment of NSCUDD, may create a danger to the health and well-being of the water Consumer. An example of a health hazard is a structural defect, including cross-connections, in a water supply system.

HAZARD, PLUMBING: A plumbing type cross-connection in a Consumer's potable water system that has not been properly protected by a vacuum breaker, air-gap separation, or backflow prevention assembly. Unprotected plumbing type cross-connections are considered to be a health hazard.

HAZARD, POLLUTION: An actual or potential threat to the physical properties of the water system or to the potability of the Public or the Consumer's potable water system, but which would constitute a nuisance or be aesthetically objectionable or could cause damage to the system or its appurtenances, but would not be dangerous to health.

HAZARD, SYSTEM: An actual or potential threat of severe damage to the physical properties of the potable water system or the Consumer's potable water system or of a pollution or contamination which would have a protracted effect on the quality of the potable water in the system.

INDUSTRIAL FLUIDS SYSTEM: Any system containing fluid or solution which may be chemically, biologically or otherwise contaminated or polluted in a form or concentration such as would constitute a health, plumbing, pollution or system hazard if introduced into the Public potable water supply.

This may include, but not be limited to, polluted or contaminated waters; all types of process waters and "used waters" originating from the public potable water system which may have deteriorated in sanitary quality; chemicals in fluid form; plating acids and alkalies, circulated cooling water connected to an open cooling tower and/or cooling towers that are chemically or biologically treated or stabilized with toxic substances; contaminated natural water such as from wells, springs, streams, rivers, bay, harbors, seas, irrigation canals or systems, etc.; oils, gases, glycerine, paraffins, caustic and acid solutions and other liquids and gaseous fluids used for industrial or other purposes or firefighting purposes.

POLLUTION: The presence of any foreign substance (organic, inorganic, or biological) in water which tends to degrade its quality so as to constitute a hazard or impair the usefulness or quality of the water to a degree which does not create an actual hazard to the public health but which does adversely and unreasonably affect such waters for domestic use.

REDUCED PRESSURE BACKFLOW ASSEMBLY: An assembly containing within its structure a minimum of two (2) independently acting approved check valves, together with an automatically operating pressure differential relief valve located between the two check valves. The first check valve reduces the supply pressure a predetermined amount so that during normal flow and at cessation of normal flow the pressure between the checks shall be less than the supply pressure.

In case of leakage of either check valve, the differential relief valve, by discharging to atmosphere, shall operate to maintain the pressure between the checks less than the supply pressure. The unit shall include tightly closing shut-off valves located at each end of the assembly, and each assembly shall be fitted with properly located test cocks.

WATER, NON-POTABLE: Water which is not safe for human consumption.

WATER, POTABLE: Any water which, according to recognized Standards, is safe for human consumption.

WATER PURVEYOR: The Owner or Operator of a Potable Water Utility supplying a potable water supply to the Public.

WATER SERVICE CONNECTIONS: The terminal end of a service connection from the potable water system; i.e., where NSCUDD loses sanitary control over the water at its point of delivery to the Customer's water system. If a meter is installed at the end of the service connection, then the service connection shall mean the downstream side of the meter. There should be no unprotected takeoffs from the service line ahead of any meter or backflow prevention assembly located at the point of delivery to the Customer's water system. Service connections shall also include all other temporary or emergency water service connections from the Public potable water system.

WATER, USED: Any water supplied by a Water Purveyor from a potable water system to a Consumer's water system after it has passed through the point of delivery and is no longer under sanitary control of the Water Purveyor.

APPENDIX A LETTERS AND FORMS

CROSS-CONNECTION CONTROL PROGRAM

LETTER TO COMMERCIAL CUSTOMER

Dear Utility Customer,

The Potable water supplied to your facility is provided by a water system owned by North Sumter County Utility Dependent District (NSCUDD). NSCUDD is responsible for the operation and maintenance of the public water supply beginning at the source and ending at the point of delivery to the customer. A critical element to operating a potable water system is to ensure the protection of the health and safety of the water supplied. One of the ways that this is achieved is by requiring that a Backflow Prevention Assembly be installed at all service connections. A Backflow Prevention Assembly is typically either a Double Check (DC) or Reduced Pressure Assembly (RP) and is located on the customer side of the water meter. Backflow Prevention Assemblies are installed on water service lines to all commercial buildings. This is further explained in the Cross-Connection Control Program Handbook that was created by NSCUDD in compliance with the rules of the Florida Department of Environmental Protection (FDEP). The Cross-Connection Control Program Handbook outlines the requirements of the customer, which includes installation and annual testing and maintenance on all Backflow Prevention Assemblies. A copy of the Cross-Connection Control Handbook can be downloaded on our website at www.DistrictGov.org by selecting the following: Departments - Utilities - Commercial Customers - and then under the heading Cross-Connection Control Handbook, select NSCUDD - Download Here.

COMMONLY ASKED QUESTIONS REGARDING CROSS-CONNECTION AND BACKFLOW

What is a cross-connection?

A cross-connection is a point in a plumbing system where the potable water supply is connected to a non-potable source.

Where might cross-connections be found?

They can be found in all plumbing systems in areas such as:

- Wash Basins and Service Sinks
- Ornamental Fountains
- Medical and Dental Equipment
- Hose Bibs
- Photo Developing Equipment
- Fire Sprinkler Systems

What is backflow?

It is the unwanted flow of non-potable or contaminated fluids back into the customer's plumbing system and/or the public water system. There are two types of backflow, see below:

- **Backsiphonage**- caused by a negative pressure in the supply line to a facility or plumbing fixture.
- **Backpressure**- can occur when the potable water supply is connected to another system operated at a higher pressure or has the ability to create pressure. Primary causes are booster pumps, pressure vessels, elevated plumbing, etc.

What is a cross-connection control program?

It is a program required by the FDEP to detect and prevent possible sources of non-potable water or contaminants from entering the public water supply.

Why do backflow assemblies need to be tested every year?

The backflow assembly is a mechanical device that needs maintenance just as a vehicle does. The annual test indicates if the internal check valves and mechanics are working properly. Annual testing and maintenance, if necessary, is also required by FDEP and NSCUDD.

NSCUDD EMERGENCY RESPONSE PROCEDURES IN THE EVENT OF AN IDENTIFIED CROSS-CONNECTION OR BACKFLOW EVENT

The following Procedures will be followed by NSCUDD personnel in the event of an identified water system cross-connection or backflow event.

1. DISCONNECT

- Eliminate the cross-connection or disconnect the backflow source.

2. REPORT

- Immediately report the incident to the following utility contacts:

CONTACT	PHONE NUMBER
VCCDD Administrative Operations Manager	(352) 751-3939
CH2M HILL Project Director	(352) 259-2802
NSCUDD Utility Engineer	(352) 753-4747
CH2M HILL Project Manager	(352) 259-2802
VCCDD Public Safety	(352) 205-8280
After Hours or Weekends - Community Watch	(352) 753-0550

- Begin documentation log at notification of cross-connection to include date, time, location, and activities associated with the event.

3. INVESTIGATION/NOTIFICATION

- Perform an investigation of the cross-connection to identify the potential contaminant and the degree of hazard.
- Do an assessment to determine the potential impact area.
- If a known contaminant has been introduced into the water system, isolate the impacted area and shut down the water system.
- Notify all affected homes and businesses regarding the system outage.
- If it cannot be determined that a contaminant has been introduced into the water system, issue a Boil Water Notice to the potentially impacted area using the following procedures:
 - Send email to the VCCDD Utilities email group identifying the incident that occurred, location of incident, and number of homes/businesses affected.
 - Provide a PSA for the billing and Customer Service Division, VCCDD Utilities email group, and the Public Safety Department.
 - Place door hangers on the front door of homes that are affected by the incident and directly contact affected businesses.
- Notify the Florida Department of Environmental Protection.
- Notify the County Health Departments at the following numbers:

HEALTH DEPARTMENT	PHONE NUMBERS
Sumter County Health Department	(352)793-7133
Marion County Health Department	(352) 629-0137
Lake County Health Department	(352) 589-6424

4. CORRECTION

- Implement technical activities to repair and correct the cross-connection or backflow event.
- Flush and decontaminate the water system as necessary.
- Perform a site inspection of the affected area to be sure the cross-connection source has been eliminated.
- Perform water samples to be sure the distribution system is free of any contaminants.

5. RESCIND NOTIFICATION

- Notify the VCCDD Utilities email group and the affected homes when the precautionary boil water notice is rescinded by placing door hangers on the front door of the homes that were affected. Businesses should be contacted directly

NSCUDD WATER SYSTEMS
CROSS-CONNECTION CONTROL SURVEY FORM

ACCOUNT
NUMBER: _____

DATE COMPLETED: _____

FACILITY NAME: _____

CONTACT NAME: _____

FACILITY
ADDRESS: _____

FACILITY PHONE: () _____ FACILITY
FAX: () _____

OWNER NAME: _____

CONTACT NAME: _____

OWNER ADDRESS: _____

OWNER PHONE: () _____ OWNER FAX: () _____

TYPE OF FACILITY: _____

DESCRIBE ACTIVITIES AT THE
FACILITY: _____

WATER SERVICE LINE SIZE (in): _____ WATER METER SIZE (in): _____

NOTE: Completion of this form in its entirety is required prior to initiation of water service

QUESTIONS

YES

NO

- | | | |
|--|--------|--------|
| 1. Is there another source of water to the property other than the service connection to the public potable supply i.e., a private well, lake, stream, river, pond, etc.? | () | () |
| 2. Is there an irrigation system on the property? | () | () |
| 3. Are there any facilities (such as a booster pump, pressure tank, etc.) that increase the water pressure to the facility or any portion thereof, above the supply pressure presently provided by the potable supply? | () | () |
| 4. Are any chemicals used in the operation? | () | () |
| 5. Are any chemicals stored at the facility? | () | () |
| 6. Are any ejectors, aspirators, or pumps used in the operation? | () | () |
| 7. Is any water recycled during the operation of an air conditioner or other equipment in your plant or building? | () | () |
| 8. Are there any water supply lines submerged in tanks, vats, etc.? | () | () |
| 9. Is there a fire stand-pipe or fire sprinkler system installed in the building? | () | () |

PROVIDE APPROPRIATE DETAILS ON ALL QUESTIONS ANSWERED "YES".
ATTACH ADDITIONAL SHEETS AS
NECESSARY:

Acknowledgement: Details regarding the Cross-Connection Control Program are contained in a handbook that has been adopted by NSCUDD. By my signature below, I acknowledge that NSCUDD has made the Cross-Connection Control Program Handbook available to me by logging on to www.DistrictGov.org and then selecting the following: Departments - Utilities - Commercial Customers - and then under the heading Cross-Connection Control Handbook, select NSCUDD - Download Here. I further agree to be bound by the conditions and guidelines included therein. I also acknowledge that the information that I have provided is correct to the best of my knowledge and may result in the requirement of additional actions. Such actions may include, but are not limited to, installation of or modification of a backflow prevention assembly. Any action, if required, will be the responsibility of the customer or facility owner, as appropriate. Actions shall be completed within 30 days of receipt of notification by NSCUDD or its designated agent.

OWNER OR AGENT: _____ TITLE: _____
(Please Print)

SIGNATURE: _____ DATE: _____

NSCUDD
REPRESENTATIVE: _____ DATE: _____

Upon completion of this form, please return the original to:

North Sumter County Utility Dependent District
Attention: Cross-Connection Control Program
1038 Lake Sumter Landing
The Villages, FL 32162
Fax: (352) 753-1296

NSCUDD POTABLE WATER SYSTEMS
BACKFLOW PREVENTION ASSEMBLY INSTALLATION RECORD

ACCOUNTNUMBER: _____

DATE COMPLETED: _____

FACILITY NAME: _____

OWNER: _____

OWNER ADDRESS: _____

OWNER PHONE: () OWNER FAX: ()

FACILITY ADDRESS / LOCATION: _____

FACILITY PHONE: () FACILITY FAX: ()

LOCATION 1

WATER SERVICE DESCRIPTION (potable indoor, pool make-up, etc.)

WATER SERVICE LINE SIZE (in): _____ WATER METER SIZE (in): _____

BACKFLOW PREVENTION ASSEMBLY:

Manufacturer: _____

Model Number: _____

Size (in): _____

Type (Double Check, Reduced Pressure Assemblies, etc.): _____

LOCATION 2

WATER SERVICE DESCRIPTION (potable indoor, pool make-up, etc.)

WATER SERVICE LINE SIZE (in): _____ WATER METER SIZE(in): _____

BACKFLOW PREVENTION ASSEMBLY:

Manufacturer: _____

Model Number: _____

Size (in): _____

Type (Double Check, Reduced Pressure Assemblies, etc.): _____

Please attach additional sheets as necessary for additional water system service connections.

Completed forms shall be submitted to:

North Sumter County Utility Dependent District
Attention: Backflow Prevention Program
1038 Lake Sumter Landing
The Villages, FL 32162
Fax: (352) 753-1296

NSCUDD POTABLE WATER SYSTEMS
BACKFLOW PREVENTION ASSEMBLY
TEST AND MAINTENANCE REPORT REQUIREMENTS

The following information should be included either on the backflow test report form provided by the backflow assembly tester, or be attached to the backflow assembly test report form. The test report form should also include all the necessary assembly testing results and requirements.

Facility and Owner Information

- Date of Test
- Facility Account Number
- Facility Name
- Facility Address
- Facility Phone Number
- Owner Name
- Owner Address
- Owner Phone Number

Assembly Description

- Location of Assembly
- Manufacturer, Model Number, and Serial Number
- Type of Assembly (Double Check, Reduced Pressure Assembly, etc.)
- Size of Assembly

Meter Information

- Meter Size
- Serial Number

Tester Information

- Company Name
- Phone Number
- Tester Name **(clearly written or typed)**
- Tester Certification Number
- Gauge Manufacturer, Model Number, and Serial Number
- Last Calibration Date of Gauge (this date must be current)

All forms shall be completed and submitted to:

North Sumter County Utility Dependent District
Attention: Backflow Prevention Program
1038 Lake Sumter Landing
The Villages, FL 32162
Fax: (352) 753-1296

APPENDIX B

APPROVED BACKFLOW PREVENTION ASSEMBLIES & INSTALLATION DETAILS

DOUBLE CHECK VALVE ASSEMBLY



Series LF2000B

Double Check Valve Assemblies

Sizes: 1/2" – 2" (15 – 60mm)

LEAD FREE*

Features

- Ease of maintenance with only one cover
- Top entry
- Replaceable seats and seat discs
- Modular construction
- Compact design
- 1/2" – 2" (15 – 50mm) Lead Free* cast silicon copper alloy body construction
- Top mounted ball valve test cocks
- Low pressure drop
- No special tools required
- 1/2" – 1" (15 – 25 mm) have tee handles



3/4" LF2000B
(20mm)

Series LF2000B Double Check Valve Assemblies shall be installed at referenced cross-connections to prevent the backflow of polluted water into the potable water supply. Only those cross-connections identified by local inspection authorities as non-health hazard shall be allowed the use of an approved double check valve assembly.

Check with local authority having jurisdiction regarding vertical orientation, frequency of testing or other installation requirements.

These valves meet the requirements of ASSE Std. 1015 and AWWA Std. C510 and are approved by the Foundation for Cross-Connection Control and Hydraulic Research at the University of Southern California. The LF2000B features Lead Free* construction to comply with Lead Free* installation requirements.

Available Models

Suffix:

B - Quarter turn ball valves

LBV - less ball valves

Pressure — Temperature

Temperature Range: 33°F – 140°F
(0.5°C – 60°C)

Maximum Working Pressure: 175psi
(12.06 bar)

Standards

AWWA Std. C510, IAPMO PS31

*The wetted surface of this product contacted by consumable water contains less than 0.25% of lead by weight.

Specifications

A Double Check Valve Assembly shall be installed at each noted location. The Double Check Valve Assemblies shall be constructed using Lead Free* materials. Lead Free* valves shall comply with state codes and standards, where applicable, requiring reduced lead content. The assembly shall consist of two positive seating check modules with captured springs and rubber seat discs. The check module seats and seat discs shall be replaceable. Service of all internal components shall be through a single access cover secured with stainless steel bolts. The assembly shall also include two resilient seated isolation valves and four top mounted, resilient seated test cocks. The assembly shall meet the requirements of ASSE Std. 1015 and AWWA Std. C510. Approved by the Foundation for Cross-Connection Control and Hydraulic Research at the University of Southern California. Assembly shall be an Ames Company Series LF2000B.

Approvals



Approved by the Foundation for Cross-Connection Control and Hydraulic Research at the University of Southern California.

LBV models not listed.

Horizontal and vertical "flow up" approval on all sizes.

Job Name _____ Contractor _____

Job Location _____ Approval _____


Engineer _____ Contractor's P.O. No. _____

Approval _____ Representative _____

Ames product specifications in U.S. customary units and metric are approximate and are provided for reference only. For precise measurements, please contact Ames Technical Service. Ames reserves the right to change or modify product design, construction, specifications, or materials without prior notice and without incurring any obligation to make such changes and modifications on Ames products previously or subsequently sold.

www.amesfirewater.com

Dimensions – Weights









LF2000B

SIZE (DN)				DIMENSIONS										WEIGHT			
		A		B		C		F		G		H		I			
<i>in.</i>	<i>mm</i>	<i>in.</i>	<i>mm</i>	<i>in.</i>	<i>mm</i>	<i>in.</i>	<i>mm</i>	<i>in.</i>	<i>mm</i>	<i>in.</i>	<i>mm</i>	<i>in.</i>	<i>mm</i>	<i>in.</i>	<i>mm</i>	<i>lbs.</i>	<i>kgs.</i>
½	15	10	254	4⅝	117	2⅞	62	5	127	3⅝	85	2⅞	59	2⅞	52	4.5	2
¾	20	11⅞	282	4	102	3⅝	79	6⅞	157	3⅞	87	2⅞	54	1⅞	33	5	2.3
1	25	13¼	337	5⅞	130	4	102	7½	191	3⅞	85	11⅞	43	11⅞	43	12	5.4
1¼	32	16⅝	416	5	127	3⅞	84	9½	241	5	127	3	76	2	50	15	6.8
1½	40	16¾	425	4⅞	124	3½	89	9¾	248	51⅞	148	3⅞	79	2⅞	68	15.86	7.2
2	50	19½	495	6¼	159	4	102	13⅞	340	6⅞	156	3⅞	87	2⅞	68	25.75	11.7

Strainer sold separately

Capacities

As compiled from documented Foundation for Cross-Connection Control and Hydraulic Research at the University of Southern California lab tests.
*Typical maximum system flow rate (7.5 feet/sec., 2.3 meters/sec.)



A Watts Water Technologies Company

www.amesfirewater.com



**ISO 9001-2008
CERTIFIED**

USA: Backflow- Tel: (916) 928-0123 • Fax: (916) 928-9333

Control Valves- Tel: (713) 943-0688 • Fax: (713) 944-9445

Canada: Tel: (905) 332-4090 • Fax: (905) 332-7068

© 2013 Ames Fire & Waterworks

Job Name _____

Contractor _____

Job Location _____

Approval _____

Engineer _____

Contractor's P.O. No. _____

Approval _____

Representative _____

LEAD FREE*

Series 2000SS

Double Check Valve Assemblies

Sizes: 2½" – 12" (65 – 300mm)

Features

- Cam-Check Assembly provides low head loss
- Short lay length is ideally suited for retrofit installations
- Stainless Steel body is half the weight of competitive designs reducing installation and shipping cost
- Stainless steel construction provides long term corrosion protection and maximum strength
- Single top access cover with two-bolt grooved style coupling for ease of maintenance
- No special tools required for servicing
- Compact construction allows for smaller vaults and enclosures
- May be installed in horizontal or vertical "flow up" position (ASSE Only)

Available Models

Suffix:

- NRS** – non-rising stem resilient seated gate valves
- OSY** – UL/FM outside stem and yoke resilient seated gate valves
- **OSY FxG** – flanged inlet gate connection and grooved outlet gate connection
- **OSY GxF** – grooved inlet gate connection and flanged outlet gate connection
- **OSY GxG** – grooved inlet gate connection and grooved outlet gate connection
- LG** – less gates

Available with grooved NRS gate valves – consult factory**

Post indicator plate and operating nut available – consult factory**

**Consult factory for dimensions

NOTICE

Inquire with governing authorities for local installation requirements

***The wetted surface of this product contacted by consumable water contains less than 0.25% of lead by weight.**

Ames Fire & Waterworks product specifications in U.S. customary units and metric are approximate and are provided for reference only. For precise measurements, please contact Ames Fire & Waterworks Technical Service. Ames Fire & Waterworks reserves the right to change or modify product design, construction, specifications, or materials without prior notice and without incurring any obligation to make such changes and modifications on Ames Fire & Waterworks products previously or subsequently sold.



2000SS

Series 2000SS Double Check Valve Assemblies are designed to prevent the reverse flow of polluted water from entering into the potable water system. This series can be applied, where approved by the local authority having jurisdiction, on non-health hazard installations. Features short end-to-end dimensions, lightweight stainless steel body, and low head loss.

Specifications

A Double Check Valve Assembly shall be installed at each noted location to prevent the unwanted reversal of polluted water into the potable water supply. The main valve body shall be manufactured from 300 series stainless steel to provide corrosion resistance, 100% lead free through the waterway. The double check shall consist of two independently operated spring loaded cam-check valves, required test cocks, and optional inlet and outlet resilient seated shutoff valves. Each cam-check shall be internally loaded and provide a positive drip tight closure against the reverse flow of liquid caused by backsiphonage or backpressure. The modular cam-check includes a stainless steel spring and cam-arm, rubber faced disc and a replaceable seat. There shall be no brass or bronze parts used within the cam-check valve assembly. The valve cover shall be held in place through the use of a single grooved style two-bolt coupling. The main assembly shall consist of two independently operating torsion spring check assemblies, two resilient seated isolation valves, and four ball valve type test cocks. The assembly shall be an Ames Company Series 2000SS.

Materials

All internal metal parts: 300 Series stainless steel

Main valve body: 300 Series stainless steel

Check assembly: Noryl®

Flange dimension in accordance with AWWA Class D

Noryl® is a registered trademark of General Electric Company.

Pressure — Temperature

Temperature Range: 33°F – 110°F (5°C – 43°C)

Maximum Working Pressure: 175psi (12.06 bar)

NOTICE

The information contained herein is not intended to replace the full product installation and safety information available or the experience of a trained product installer. You are required to thoroughly read all installation instructions and product safety information before beginning the installation of this product.

Standards

AWWA C510-92, CSA B64.5

Approvals



1015



(OSY ONLY)










Approved

For 12" approvals
consult factory




Capacities

Rated working pressure 175psi (12.06 bar) * Rated flow **UL Tested



Dimensions — Weights



SIZE (DN)		DIMENSIONS										WEIGHT					
		A		C (OSY)		C(NRS)		D		L		S		w/Gates		w/o Gates	
<i>in.</i>	<i>mm</i>	<i>in.</i>	<i>mm</i>	<i>in.</i>	<i>mm</i>	<i>in.</i>	<i>mm</i>	<i>in.</i>	<i>mm</i>	<i>in.</i>	<i>mm</i>	<i>in.</i>	<i>mm</i>	<i>lb.</i>	<i>kg.</i>	<i>lb.</i>	<i>kg.</i>
2½	65	37	965	16¾	416	9¾	238	3½	89	22	559	7	178	140	64	53	24
3	80	38	965	18¾	479	10¼	260	3¾	95	22	559	7½	191	215	98	55	25
4	100	40	1016	22¾	578	12¾ ₁₆	310	4½	114	22	559	9	229	225	102	58	26
6	150	48½	1232	30¾	765	16	406	5½	140	27½	699	11	279	375	170	105	48
8	200	52½	1334	37¾	959	19 ¹⁵ / ₁₆	506	6¾	171	29½	749	13½	343	561	254	169	77
10	250	55½	1410	45¾	1162	23 ¹³ / ₁₆	605	8	200	29½	749	16	406	763	346	179	81
12	300	57½	1461	53¾	1349	26¾	679	9½	241	29½	749	19	483	1033	469	209	95



A WATTS Brand

For Non-Health Hazard Applications

Job Name _____

Contractor _____

Job Location _____

Approval _____

Engineer _____

Contractor's P.O. No. _____

Approval _____

Representative _____

LEAD FREE*

Series 850

Double Check Valve Assemblies

Size: ½" - 2" (15mm - 50mm)

The FEBCO Series 850 Double Check Valve Assemblies are designed for non-health hazard applications. End Connections – NPT ANSI / ASME B1.20.1

Pressure – Temperature

Max. Working Pressure: 175psi (12.1 bar)
Hydrostatic Test Press: 350psi (24.1 bar)
Temperature Range: 32°F to 140°F (0°C to 60°C)

Materials

Valve Body: Bronze
Elastomers: Silicone
Springs: Stainless Steel

Models


- Wye - Strainer

Approvals – Standards

- ANSI/AWWA Conformance (C510-92)
- Approved by the Foundation for Cross-Connection Control and Hydraulic Research at the University of Southern California.




Typical Installation



WARNING







It is illegal to use this product in any plumbing system providing water for human consumption, such as drinking or dishwashing, in the United States. Before installing standard material product, consult your local water authority, building and plumbing codes.

FEBCO product specifications in U.S. customary units and metric are approximate and are provided for reference only. For precise measurements, please contact FEBCO Technical Service. FEBCO reserves the right to change or modify product design, construction, specifications, or materials without prior notice and without incurring any obligation to make such changes and modifications on FEBCO products previously or subsequently sold.




Series 850

Capacity




A WATTS Brand


Series 850 / Size: ½" - 2" (15mm - 50mm)



ITEM	DESCRIPTION	MATERIALS
1	Body	Bronze
1.2	Tailpiece	Bronze
1.4	O-Ring	Silicone
2	Cover	Bronze
2.2	O-Ring	Silicone
3	Seat	Noryl®
3.1	O-Ring	Silicone
4	Poppet	Noryl®
5	Seat Disc	Silicone
5.1	Disc Retainer	Noryl®
5.2	Rnd HD Screw	Stainless Steel
6	Spring	Stainless Steel
7	Guide	Noryl®
8	Retainer Spacer	Noryl®
9	Ball Valve (w/tap)	Bronze
9.1	Ball Valve	Bronze
11	Test Cock	Bronze
21	Hex HD Capscrew	Stainless Steel
60	Identification Plate	Brass
61	Drive Screw Stick	Stainless Steel



Check Assembly



Dimensions and Weights

Size: ½" - 2" (15 - 50mm)

SIZE (DN)		DIMENSIONS										WEIGHT	
		A		B		C		D		E			
in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	lbs.	kgs.
½	15	10	254	1½	38	1½	38	3⅞	79	1¼	32	4.2	1.9
¾	20	10¾	273	1½	38	1½	38	3⅞	79	1¼	32	4.4	2.0
1	25	12½	318	1⅞	48	1⅞	41	3⅞	86	1½	38	6.8	3.1
1¼	32	15⅞	403	3	76	2½	64	4¼	108	2¼	57	15.8	7.2
1½	40	16⅞	416	3	76	2½	64	4¼	108	2¼	57	16.2	7.4
2	50	17⅞	450	3½	89	2½	64	4¼	108	2¼	57	21.1	9.6

Dimensions are nominal. Allowances must be made for normal manufacturing tolerances.



A WATTS Brand

USA: Tel: (800) 767-1234 • Fax: (800) 788-4491 • FEBCOonline.com
 Canada: Tel: (905) 332-4090 • Fax: (905) 332-7068 • FEBCOonline.ca
 Latin America: (52) 81-1001-8600 • Fax: (52) 81-8000-7091 • FEBCOonline.com

For Non-Health Hazard Applications

Job Name _____

Contractor _____

Job Location _____

Approval _____

Engineer _____

Contractor's P.O. No. _____

Approval _____

Representative _____

LEAD FREE*

MasterSeries® LF850

Double Check Valve Backflow Prevention Assemblies

Sizes: 2½" – 10"

The FEBCO MasterSeries LF850 Double Check Assembly is specifically designed to protect against possible backpressure and backsiphonage conditions for non-health hazard (i.e., pollutant) application in accordance with Local Governing Water Utility Code. This Backflow Assembly is primarily used on potable drinking water systems where Local Governing Code mandates protection from non-potable quality water being pumped or siphoned back into the potable water system.

The LF850 features Lead Free* construction to comply with low lead installation requirements. The Lead Free* Double Check Assemblies shall comply with state codes and standards, where applicable, requiring reduced lead content.

Features

- Inline Serviceable Assembly
- No Special Tools Required for Servicing
- Captured Modular Spring Assembly
- Reversible & Replaceable Discs
- Field Replaceable Seats
- Ductile Iron Valve Body Design
- Stainless Steel Check Components
- Winterization feature with disc retainers and valve body drain ports
- Clapper Check Assembly
- Commonality between 1st & 2nd Check Components
- Captured O-ring Design

MASTER series®



Model LF850 Double Check Assembly

Specifications

The FEBCO MasterSeries LF850 Double Check Valve Assembly shall be installed on the potable water supply and at each point of cross-connection to protect against possible backpressure and backsiphonage conditions for non-health hazard (i.e., pollutant) applications. The assembly shall consist of a main line valve body composed of two (2) independently acting approved clapper style check modules with replaceable seats and disc rubbers. Servicing of both check modules does not require any special tools and are accessed through independently top entry covers. This assembly shall be fitted with AWWA Compliant inlet/outlet resilient seated shutoff valves; when used on a Fire-Sprinkler application, the assembly shall be fitted with approved UL/FM inlet/outlet resilient seated shutoff valves and contain four (4) properly located resilient seated test cocks as specified by AWWA Standard C510. Flow and pressure loss performance parameters shall meet the requirements of AWWA Standard C510.

NOTICE

The information contained herein is not intended to replace the full product installation and safety information available or the experience of a trained product installer. You are required to thoroughly read all installation instructions and product safety information before beginning the installation of this product.

NOTICE

Inquire with governing authorities for local installation requirements

*The wetted surface of this product contacted by consumable water contains less than 0.25% of lead by weight.

FEBCO product specifications in U.S. customary units and metric are approximate and are provided for reference only. For precise measurements, please contact FEBCO Technical Service. FEBCO reserves the right to change or modify product design, construction, specifications, or materials without prior notice and without incurring any obligation to make such changes and modifications on FEBCO products previously or subsequently sold.



A WATTS Brand

Options - Suffix

- OSY: UL/FM Approved OS&Y Gate Valves
(ANSI/AWWA C515 Compliant)
- NRS: Non-Rising Stem Gate Valves
(ANSI/AWWA C509 Compliant)
- LG: Less Shut-off valves; This is NOT an APPROVED
ASSEMBLY

Example Ordering Descriptions:

- 4" LF850-OSY - Valve Assembly fitted with OS&Y Shutoff Valves
- 4" LF850-NRS - Valve Assembly fitted with NRS Shutoff Valves

Assembly Flow Orientation:

Horizontal & Vertical Up (2½" – 10") - Approved by FCCCHR-
USC, ASSE, cULus, FM, IAPMO, and CSA

Approvals – Standards

- Approved by the Foundation for Cross-Connection Control and Hydraulic Research at The University of Southern California (FCCCHR-USC)
 - ASSE 1015 Listed
 - **UL Classified (US & Canada)
 - **FM Approved
 - IAPMO
 - CSA Listed
 - AWWA Standard C510 Compliant
 - End Connections: Compliant to ASME B16.1 Class 125 & AWWA Class D Flange
- **Assembly configured with UL/FM Approved OS&Y RW Gate Valves. Less gate valve assemblies are not UL/FM approved configurations.




Materials

Below is a general materials list of the Model LF850. All assemblies size 2½" through 10" is similar in materials and construction. Please contact your local FEBCO Representative if you require further information.

- Main Valve Body: Ductile iron Grade 65-45-12
- Coating: Fusion epoxy coated internal and external
AWWA C550
- Shutoff Valves: NRS resilient wedge gate valves AWWA C509
(Standard)
OSY resilient wedge gate valves AWWA C515
(UL/FM)
- Check Seats: Stainless Steel
- Disc Holder: Stainless Steel
- Elastomer Disc: Silicone
- Spring: Stainless Steel
- Clamp: AWWA C606 (10" Only)

Pressure – Temperature

- Max. Working Pressure: 175psi (12.1 bar)
- Min. Working Pressure: 10psi (0.7 bar)
- Hydrostatic Test Pressure: 350psi (24.1 bar)
- Hydrostatic Safety Pressure: 700psi (48.3 bar)
- Temperature Range: 33°F - 140°F (0.5°C - 60°C)
Continuous



Model 950XLT2

Top Access Double Check Valve Assembly

Application

Ideal for use where Lead-Free* valves are required. Designed for installation on potable water lines to protect against both backsiphonage and backpressure of polluted water into the potable water supply. A test cock plug is provided to protect against fouling caused by insects, dirt and debris. Assembly shall provide protection where a potential non-health hazard exists.


Standards Compliance

- (Unless otherwise noted, applies to 3/4" thru 2" Horizontal)
- ASSE® Listed 1015 (Vertical flow-up: 1 1/4" thru 2")
- IAPMO® Listed
- CSA® Certified (Vertical flow-up: 1 1/2" & 2")
- AWWA Compliant C510
- Approved by the Foundation for Cross Connection Control and Hydraulic Research at the University of Southern California
- Meets the requirements of NSF/ANSI 61*

*(0.25% MAX. WEIGHTED AVERAGE LEAD CONTENT)

Materials

Main valve body	Low Lead Cast Bronze ASTM B 584
Access covers	Low Lead Cast Bronze ASTM B 584
Fasteners	Stainless Steel, 300 Series
Elastomers	Silicone (FDA approved)
	Buna Nitrile (FDA approved)
Polymers	Noryl™
Springs	Stainless steel, 300 series
Test cock cover	Plastic
Ball valve handles	Stainless steel



Features

Sizes: 3/4", 1", 1 1/4", 1 1/2", 2"	
Maximum working water pressure	175 PSI
Maximum working water temperature	180°F
Hydrostatic test pressure	350 PSI
End connections Threaded	ANSI B1.20.1


Options (Suffixes can be combined)

- ☐ FT - with "Fast Test" test cocks
- ☐ S - with Model SXL lead-free bronze "Y" type strainer
- ☐ PF - with Z-Bite™ push fit connections* (1/2"-1" only)
- ☐ PR - with Z-Press™ press fit connections*

*Fittings ship in box with valve and must be threaded into valve by hand on site.

Accessories

- ☐ Repair kit (rubber only)
- ☐ Thermal expansion tank (Model XT)
- ☐ QT-SET Quick Test Fitting Set





Dimensions & Weights (do not include pkg.)

MODEL SIZE		DIMENSIONS (approximate)														WITH BALL VALVES	
		A		B		C		D		E		F		G			
		in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	lbs.	kg
3/4	20	13	330	8 3/4	222	2 3/8	60	2 5/16	59	3 5/16	84	3/4	19	17 5/8	448	6	2.7
1	25	14	356	8 3/4	222	2 1/2	64	2 5/16	59	3 5/16	84	3/4	19	19 3/4	502	12	5.4
1 1/4	32	19 5/8	499	13 3/4	349	4	102	3 5/8	92	4 3/8	111	1 5/16	33	24 3/4	629	22	10
1 1/2	40	20 5/16	516	13 3/4	349	5 3/8	137	3 5/8	92	4 3/8	111	1 5/16	33	25 15/16	659	22	10
2	50	21 3/8	543	13 3/4	349	5 13/16	148	3 5/8	92	4 3/8	111	1 5/16	33	28 5/16	719	29	13.2

MODEL 950XLT2 3/4", 1", 1 1/4", 1 1/2" & 2" (STANDARD & METRIC)

FLOW RATES (l/s)





FLOW RATES (GPM)

Typical Installation

Local codes shall govern installation requirements. To be installed in accordance with the manufacturer's instructions and the latest edition of the Uniform Plumbing Code. Unless otherwise specified, the assembly shall be mounted at a minimum of 12" (305mm) and a maximum of 30" (762mm) above adequate drains with sufficient side clearance for testing and maintenance. If installed below grade, be certain adequate drainage is provided to prevent the device from being submerged.

Capacity thru Schedule 40 Pipe				
Pipe size	5 ft/sec	7.5 ft/sec	10 ft/sec	15 ft/sec
1/8"	1	1	2	3
1/4"	2	2	3	5
3/8"	3	4	6	9
1/2"	5	7	9	14
3/4"	8	12	17	25
1"	13	20	27	40
1 1/4"	23	35	47	70
1 1/2"	32	48	63	95
2"	52	78	105	167

**OUTDOOR INSTALLATION****PIT INSTALLATION****Specifications**

The Double Check Type Backflow Preventer shall be certified to NSF/ANSI 61, shall be ASSE Listed 1015, rated to 180°F, and supplied with full port ball valves. The main body and access covers shall be low lead bronze (ASTM B 584), the seat ring and all internal polymers shall be Noryl™ and the seat disc elastomers shall be SILICONE. The first and second check shall be located at a 45° angle and accessible for maintenance from the top of the device, without removing the device from the line. Each check shall have separate access covers and test cocks shall be accessible from the top of the device. Test cocks shall be protected from debris by a plug. The Double Check Type Backflow Preventer shall be a ZURN WILKINS Model 950XLT2.

REDUCED PRESSURE ASSEMBLY



Series LF4000B

Reduced Pressure Zone Assemblies

Sizes: 1/2" – 2"

LEAD FREE*

Features

- Single access cover and modular check construction for ease of maintenance
- Top entry - all internals immediately accessible
- Captured springs for safe maintenance
- Internal relief valve for reduced installation clearances
- Replaceable seats for economical repair
- Lead Free* cast silicon copper alloy construction for durability - 1/2" to 2"
- Ball valve test cocks - screwdriver slotted - 1/2" to 2"
- Large body passages provides low pressure drop
- Compact, space saving design
- No special tools required for servicing

Available Models

Suffix:

B - quarter-turn ball valves

Pressure — Temperature

Suitable for supply pressures up to 175psi (12.1bar) and water temperature to 180°F (75°C) continuous.

Standards

AWWA C511, IAPMO File No. 1563

*The wetted surface of this product contacted by consumable water contains less than 0.25% of lead by weight.

NOTICE

The information contained herein is not intended to replace the full product installation and safety information available or the experience of a trained product installer. You are required to thoroughly read all installation instructions and product safety information before beginning the installation of this product.



1/2" LF4000B
(15mm)

Series LF4000B Reduced Pressure Zone Assemblies are designed to protect potable water supplies in accordance with national plumbing codes and water authority requirements. This series can be used in a variety of installations, including the prevention of health hazard cross connections in piping systems or for containment at the service line entrance.

This series features two in-line, independent check valves, captured springs and replaceable check seats with an intermediate relief valve. Its compact modular design facilitates easy maintenance and assembly access. Sizes 1/2" - 1" shutoffs have tee handles. The LF4000B features Lead Free* construction to comply with Lead Free* installation requirements.

Specifications

A Reduced Pressure Zone Assembly shall be installed at each potential health hazard location to prevent backflow due to backsiphonage and/or backpressure. Lead Free* Reduced Pressure Zone Assembly shall be constructed using Lead Free* materials. Lead Free assemblies shall comply with state codes and standards, where applicable, requiring reduced lead content. The assembly shall consist of an internal pressure differential relief valve located in a zone between two positive seating check modules with captured springs and silicone seat discs. Seats and seat discs shall be replaceable in both check modules and the relief valve. There shall be no threads or screws in the waterway exposed to line fluids. Service of all internal components shall be through a single access cover secured with stainless steel bolts. The assembly shall also include two resilient seated isolation valves, four resilient seated test cocks and an air gap drain fitting. The assembly shall meet the requirements of: USC; ASSE Std. 1013; AWWA Std. C511; CSA B64.4. The assembly shall be an Ames Company Series LF4000B.

Approvals

Approved by the Foundation for Cross-Connection Control and Hydraulic Research at the University of Southern California.



Job Name _____ Contractor _____

Job Location _____ Approval _____


Engineer _____ Contractor's P.O. No. _____

Approval _____ Representative _____

Ames product specifications in U.S. customary units and metric are approximate and are provided for reference only. For precise measurements, please contact Ames Technical Service. Ames reserves the right to change or modify product design, construction, specifications, or materials without prior notice and without incurring any obligation to make such changes and modifications on Ames products previously or subsequently sold.

www.amesfirewater.com

Weights — Dimensions









LF4000B

SIZE		DIMENSIONS								WEIGHT	
		A		B		C		D		L	
in.		in.	mm	in.	mm	in.	mm	in.	mm	in.	mm
1/2		10	250	4 1/4	117	3 3/8	86	1 1/4	32	5 1/2	140
3/4		10 3/4	273	5	127	3 1/2	89	1 1/2	38	6 1/4	171
1		14 1/2	368	5 1/2	140	3	76	2 1/2	64	9 1/2	241
1 1/4		17 3/4	44	116	150	3 1/2	89	2 1/2	64	11 3/8	289
1 1/2		17 3/8	454	6	150	3 1/2	89	2 1/2	64	11 1/8	283
2		21 3/8	543	7 3/4	197	4 1/2	114	3 3/4	83	13 1/2	343
										lbs.	kg.
										4.50	2.0
										5.75	2.6
										12.25	5.6
										14.62	6.6
										16.32	7.4
										30.00	13.6

Strainer sold separately

Capacity

Performance as established by an independent testing laboratory. ΔTypical maximum system flow rate (7.5 feet/sec., 2.3 meters/sec.)



www.amesfirewater.com



ISO 9001-2008
CERTIFIED

A Watts Water Technologies Company

USA: Backflow- Tel: (916) 928-0123 • Fax: (916) 928-9333

Control Valves- Tel: (713) 943-0688 • Fax: (713) 944-9445

Canada: Tel: (905) 332-4090 • Fax: (905) 332-7068

ES-A-LF4000B 1406

© 2014 Ames Fire & Waterworks



Series 4000SS

Reduced Pressure Zone Assemblies

Sizes: 2½" – 10" (65 – 250mm)

LEAD FREE*

Features

- Stainless steel construction provides long term corrosion resistance and maximum strength
- Stainless steel body is half the weight of competitive designs reducing installation & shipping costs
- Short end-to-end dimensions makes retrofit easy
- Cam-check assembly provides maximum flow at low pressure drop
- No special tools required for servicing
- Compact construction allows for smaller enclosures
- Stainless steel relief valve features a balanced rolling diaphragm to eliminate sliding seals and lower maintenance costs

Available Models

Suffix:

- NRS – non-rising stem resilient seated gate valves
- OSY – UL/FM outside stem and yoke resilient seated gate valves
- **OSY FxG – flanged inlet gate connection and grooved outlet gate connection
- **OSY GxG – grooved inlet gate connection and flanged outlet gate connection
- **OSY GxG – grooved inlet gate connection and grooved outlet gate connection
- LG – less gates

Available with grooved NRS gate valves - consult factory**
Post indicator plate and operating nut available – consult factory**

**Consult factory for dimensions

NOTICE

The installation of a drain line is recommended. When installing a drain line, an air gap is necessary. The 4000SS should be installed with a minimum clearance of 12" between lowest point of the assembly and the floor drain or grade.

*The wetted surface of this product contacted by consumable water contains less than (0.25%) of lead by weight.



Series 4000SS Reduced Pressure Zone Assemblies are designed to provide protection of the potable water supply in accordance with national codes. This series can be used where approved by the local authority having jurisdiction on health-hazard cross-connections. Series 4000SS features short lay length, lightweight stainless steel body, corrosive resistant stainless steel relief valve, and patented cam-check assembly.

Specifications

A Reduced Pressure Zone Assembly shall be installed at each cross-connection to prevent backsiphonage and backpressure of hazardous materials into the potable water supply. The series 4000SS features Lead Free* construction to comply with Lead Free* installation requirements. The assembly shall consist of a pressure differential relief valve located in a zone between two positive seating cam-check assemblies. The main valve body shall be manufactured from 300 Series stainless steel for corrosion resistance. The cam-check assembly shall be of thermoplastic construction with stainless steel hinge pins, cam arm, and cam bearing. The cam-check assembly shall utilize a single torsion spring design to minimize pressure drop through the assembly. The cam-check assembly shall be modular and shall seal to the main valve body by the use of an O-ring. There shall be no brass or bronze parts used within the check assembly or relief valve. The use of seat screws to retain the check valve seat is prohibited. All internal parts shall be accessible through a single cover on the valve assembly securely held in place by a two-bolt grooved coupling. The differential relief valve shall be of stainless steel construction and shall utilize a rolling diaphragm and no sliding seals. The relief valve shall be bottom mounted and supplied with a steel reinforced sensing hose. The assembly shall include two resilient seated shutoff valves & four ball type test cocks. The assembly shall be an Ames Company Series 4000SS.

Standards

AWWA C511-92

Approvals



1013



B64.5



Sizes 2½" – 10", only



OSY OSY only

NOTICE

When installing a drain line on Series 4000SS backflow preventer, use air gap. See Literature ES-A-AG/EL/TC for additional information.

Job Name _____ Contractor _____

Job Location _____ Approval _____

Engineer _____ Contractor's P.O. No. _____

Approval _____ Representative _____

Ames product specifications in U.S. customary units and metric are approximate and are provided for reference only. For precise measurements, please contact Ames Technical Service. Ames reserves the right to change or modify product design, construction, specifications, or materials without prior notice and without incurring any obligation to make such changes and modifications on Ames products previously or subsequently sold.

amesfirewater.com

Materials

All internal metal parts: 300 Series stainless steel

Main valve body: 300 Series stainless steel

Check assembly: Noryl®

Flange dimension in accordance with AWWA Class D




Capacity

Series 4000SS performance as established by an independent testing laboratory (1996 UL). UL certified flow characteristics.

Documented flow characteristics (including shutoff valves).

*UL Rated





**UL Tested



Pressure — Temperature

Temperature Range: 33°F – 110°F (0.5°C – 43°C)

Maximum Working Pressure: 175psi (12.1 bar)




Dimensions – Weights

Note: Strainer sold separately

SIZE		DIMENSIONS										NET WEIGHT					
		A		C (OSY)		C(NRS)		D		F		L		w/Gates		w/o Gates	
in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	lb.	kg.	lb.	kg.
2½	65	37	940	16¾	416	9¾	238	10½	267	7	178	22	559	148	67	60	27
3	80	38	965	18¾	479	10¼	260	10½	267	7½	191	22	559	226	103	62	28
4	100	40	1016	22¾	578	12¾ ₁₆	310	10½	267	9	229	22	559	235	107	65	30
6	150	48½	1232	30¾	765	16	406	11½	292	11	279	27½	699	380	172	110	50
8	200	52½	1334	37¼	959	19½ ₁₆	506	12½	318	13½	343	29½	749	571	259	179	81
10	250	55½	1410	45¾	1162	23¾ ₁₆	605	12½	318	16	406	29½	749	773	351	189	86

Noryl® is a registered trademark of General Electric Company



A Watts Water Technologies Company

NOTICE

Inquire with governing authorities for local installation requirements

USA: Backflow Tel: (978) 689-6066 • Fax: (978) 975-8350 • AmesFireWater.com
USA: Control Valves Tel: (713) 943-0688 • Fax: (713) 944-9445 • AmesFireWater.com
Canada: Tel: (905) 332-4090 • Fax: (905) 332-7068 • AmesFireWater.ca
Latin America: Tel: (52) 81-1001-8600 • Fax: (52) 81-8000-7091 • AmesFireWater.com

For Health Hazard Applications

Job Name _____

Contractor _____

Job Location _____

Approval _____

Engineer _____

Contractor's P.O. No. _____

Approval _____

Representative _____

LEAD FREE*

Series LF860

Reduced Pressure Zone Assemblies

Size: 1/2" - 2"

The FEBCO Series LF860 Reduced Pressure Zone Assemblies are designed for use in health-hazard applications. The LF860S features Lead Free* construction to comply with Lead Free* installation requirements. End Connections – NPT ANSI / ASME B1.20.1. The Lead Free* Reduced Pressure Zone Assemblies shall comply with state codes and standards, where applicable, requiring reduced lead content.

Pressure – Temperature

Max. Working Pressure: 175psi (12.1 bar)
Hydrostatic Test Pressure: 350psi (24.1 bar)
Temperature Range: 32°F to 140°F (0°C to 60°C)

Materials

Valve Body: Lead Free* Cast Copper Silicon Alloy
Elastomers: Silicone
Springs: Stainless Steel

Models


- LF860 - Standard Assembly with Ball Valves
- LF860U - Standard Assembly with Union Ball Valves

Approvals – Standards

- ANSI/AWWA Conformance (C511)
- Approved by the Foundation for Cross-Connection Control and Hydraulic Research at the University of Southern California.









Typical Installation



Series LF860


Capacity




A WATTS Brand

FEBCO product specifications in U.S. customary units and metric are approximate and are provided for reference only. For precise measurements, please contact FEBCO Technical Service. FEBCO reserves the right to change or modify product design, construction, specifications, or materials without prior notice and without incurring any obligation to make such changes and modifications on FEBCO products previously or subsequently sold.


Series LF860 / Size: ½" - 2"



Relief Valve Assembly



Check Assembly



ITEM	DESCRIPTION	MATERIALS
1	Body	Lead Free* Cast Copper Silicon Alloy
1.2	Tailpiece	Lead Free* Cast Copper Silicon Alloy
1.4	O-Ring	Silicone
2	Cover	Lead Free* Cast Copper Silicon Alloy
2.2	O-Ring	Silicone
3	Seat	Noryl®
3.1	O-Ring	Silicone
4	Poppet	Noryl®
5	Seat Disc	Silicone Rubber
5.1	Disc Retainer	Noryl®
5.2	Rnd HD Screw	Phillips, 18-8 SS
6	Spring	SS
6.1	Spring	SS
7	Guide	Noryl®
8	Retainer Spacer	Noryl®
9	Ball Valve (w/tap)	Lead Free* Cast Copper Silicon Alloy
9.1	Ball Valve	Lead Free* Cast Copper Silicon Alloy
11	Test Cock	Lead Free* Cast Copper Silicon Alloy
12	Seat Ring-RV	Noryl®
12.1	Gasket Ring-RV	Silicone Rubber
13	Spring-RV	SS
14	Seat Disc-RV	Silicone Rubber/SS
15	Diaphragm-RV	Rubber/Fabric
16	Outer Diaphragm-RV	Rubber/Fabric
17	Small Piston-RV	Noryl®
17.1	Rnd HD Screw	Phillips, 18-8 SS
17.2	Washer	18-8 SS
17.3	Hex Nut	18-8 SS
18	Cylinder-RV	Lead Free* Cast Copper Silicon Alloy
18.1	Slip Ring-Cylinder	Acetal
18.2	Slide (Plug)	Nylon
19	Cover-RV	Lead Free* Cast Copper Silicon Alloy
20	O-Ring	Silicone
21	Hex HD Capscrew	18-8 SS
22	Large Piston-RV	Noryl®
23	Guide-RV	Noryl®
60	Identification Plate	Brass
61	Drive Screw Stick	SS

* The wetted surface of this product contacted by consumable water contains less than 0.25% of lead by weight.

Noryl® is a registered trademark of SABIC Innovative Plastics™.

NOTICE

The gap drain is not designed to catch the maximum discharge possible from the relief valve. The installation of FEBCO air gap with the drain line terminating above a floor drain will handle any normal discharge or nuisance spitting through the relief valve. However, floor drain size may need to be designed to prevent water damage caused by a catastrophic failure condition. Do not reduce the size of the drain line from the air gap fitting.

NOTICE

Inquire with governing authorities for local installation requirements.

NOTICE

The information contained herein is not intended to replace the full product installation and safety information available or the experience of a trained product installer. You are required to thoroughly read all installation instructions and product safety information before beginning the installation of this product.

Dimensions – Weights

Size: ½" - 2"

SIZE	DIMENSIONS										WEIGHT	
	A		B		C		D		E			
	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	lbs.	kgs.
½	10	254	1½	38	1½	38	3½	79	3½	89	5.6	2.5
¾	10¾	273	1½	38	1½	38	3½	79	3½	89	5.8	2.6
1	12½	318	1¾	48	1¾	41	3¾	86	3¾	92	9.2	4.2
1¼	15¾	403	3	76	2½	64	4¼	108	5%	143	20.2	9.2
1½	16¾	416	3	76	2½	64	4¼	108	5%	143	20.6	9.4
2	17¾	450	3½	89	2½	64	4¼	108	5%	143	24.8	11.3

Note: Dimensions are nominal. Allowances must be made for normal manufacturing tolerances.



A WATTS Brand

USA: Tel: (800) 767-1234 • Fax: (800) 788-4491 • FEBCOonline.com
Canada: Tel: (905) 332-4090 • Fax: (905) 332-7068 • FEBCOonline.ca
Latin America: (52) 81-1001-8600 • FEBCOonline.com

For Non-Health Hazard Applications

Job Name _____

Contractor _____

Job Location _____

Approval _____

Engineer _____

Contractor's P.O. No. _____

Approval _____

Representative _____

LEAD FREE*

MasterSeries® LF860

Reduced Pressure Zone Backflow Prevention Assemblies

Size: 2½" - 10" (65mm - 250mm)

The FEBCO MasterSeries LF860 Reduced Pressure Zone Assembly is specifically designed to protect against possible backpressure and backsiphonage conditions for high hazard [i.e., toxic] application in accordance with Local Governing Water Utility Code. This Backflow Prevention Assembly is primarily used on potable drinking water systems where Local Governing Code mandates protection from non-potable water being pumped or siphoned back into the potable water system.

The LF860 features Lead Free* construction to comply with low lead installation requirements. The Lead Free* Reduced Pressure Zone Assemblies shall comply with state codes and standards, where applicable, requiring reduced lead content.

Features

- Inline Serviceable Assembly
- No Special Tools Required for Servicing
- Captured Modular Spring Assembly
- Reversible & Replaceable Discs
- Field Replaceable Seats
- Ductile Iron Valve Body Design
- Stainless Steel Check Components
- Modular Pressure Differential Relief Valve
- Repairable Pressure Differential Relief Valve
- Clapper Check Assembly
- Captured O-ring Design

MASTER
series®



Series LF860 Reduced Pressure Zone Assembly

Specifications

The FEBCO MasterSeries LF860 Reduced Pressure Zone Assembly shall be installed on the potable water supply and at each point of cross-connection to protect against possible backpressure and backsiphonage conditions for high hazard [i.e., toxic] applications. The assembly shall consist of a main line valve body composed of a pressure differential relief valve located in a zone between two (2) independently acting approved clapper style check modules with replaceable seats and disc rubbers. Servicing of the pressure differential relief valve and both check modules does not require any special tools; both check modules are accessed through independently top entry covers. This assembly shall be fitted with AWWA Compliant inlet/outlet resilient seated shutoff valves; when used on a Fire-Sprinkler application, the assembly shall be fitted with approved UL/FM inlet/outlet resilient seated shutoff valves and contain four (4) properly located resilient seated test cocks as specified by AWWA Standard C511. Flow and pressure loss performance parameters shall meet the requirements of AWWA Standard C511.

NOTICE

The information contained herein is not intended to replace the full product installation and safety information available or the experience of a trained product installer. You are required to thoroughly read all installation instructions and product safety information before beginning the installation of this product.

NOTICE

Inquire with governing authorities for local installation requirements

*The wetted surface of this product contacted by consumable water contains less than 0.25% of lead by weight.

FEBCO product specifications in U.S. customary units and metric are approximate and are provided for reference only. For precise measurements, please contact FEBCO Technical Service. FEBCO reserves the right to change or modify product design, construction, specifications, or materials without prior notice and without incurring any obligation to make such changes and modifications on FEBCO products previously or subsequently sold.



A WATTS Brand

Options - Suffix

- OSY: UL/FM Approved OS&Y Gate Valves
(ANSI/AWWA C515 Compliant)
- NRS: Non-Rising Stem Gate Valves
(ANSI/AWWA C509 Compliant)
- LG: Less Shut-off valves; This is NOT an APPROVED ASSEMBLY

Example Ordering Descriptions:

- 4" LF860-OSY - Valve Assembly fitted with OS&Y Shutoff Valves
- 4" LF860-NRS - Valve Assembly fitted with NRS Shutoff Valves

Assembly Flow Orientation:

- Horizontal (2½" – 10") - Approved by FCCCHR-USC, ASSE, cULus, FM, IAPMO and CSA

Approvals - Standards

- Approved by the Foundation for Cross-Connection Control and Hydraulic Research at The University of Southern California (FCCCHR-USC)
 - ASSE 1013 Listed
 - **UL Classified (US & Canada)
 - **FM Approved
 - IAPMO
 - AWWA Standard C511 Compliant
 - End Connections: Compliant to ASME B16.1 Class 125 & AWWA Class D Flange
- **Assembly configured with UL/FM Approved OS&Y RW Gate Valves. Less gate valve assemblies are not UL/FM approved configurations.




Materials

Below is a general materials list of the Series LF860. All assemblies size 2½" through 10" is similar in materials and construction. Please contact your local FEBCO Representative if you require further information.

- Main Valve Body: Ductile iron Grade 65-45-12
- Relief Valve Body: Ductile iron Grade 65-45-12
- Coating: Fusion epoxy coated internal and external AWWA C550
- Shutoff Valves: NRS resilient wedge gate valve AWWA C509 (Standard)
OSY resilient wedge gate valve AWWA C515 (UL/FM)
- Check Seats: Stainless Steel
- Disc Holder: Stainless Steel
- Elastomer Disc: Silicone
- Spring: Stainless Steel
- Clamp: AWWA C606 (10" Only)


Pressure - Temperature

- Max. Working Pressure: 175 psi (12.1 bar)
- Min. Working Pressure: 20 psi (1.4 bar)
- Hydrostatic Test Pressure: 350 psi (24.1 bar)
- Hydrostatic Safety Pressure: 700 psi (48.3 bar)
- Temperature Range: 33°F - 140°F (0.5°C - 60°C)
Continuous



Dimensions & Weights

Below are the nominal dimensions and physical weights for the Series LF860 size 2½" through 10". Allowances must be made for normal manufacturing tolerances. Please visit our website to download a copy of this product's installation instructions, or contact your local FEBCO Representative for more information.



LF860

SIZE (DN)		DIMENSIONS																WEIGHT***			
		A		B		C		D		E*		F**		G		H		NRS		OSY	
in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	lbs.	kg.	lbs.	kg.
2½	65	40¾	1035	25½	648	10	254	10	254	12⅝	321	16⅜	416	4½	114	7⅞	181	250	113	254	115
3	80	41⅞	1064	25⅝	651	10	254	10	254	12⅞	327	22¼	565	4½	114	7⅞	187	276	125	280	127
4	100	46¼	1175	28	711	10⅞	257	10⅞	257	14⅜	365	23¼	591	5½	140	8⅞	206	335	152	347	157
6	150	56	1422	34¾	883	12¾	324	11⅞	283	18⅞	479	30⅞	765	6½	165	9⅞	251	503	228	523	237
8	200	65	1651	41¾	1061	15⅝	397	12¼	311	23½	597	37¾	959	7	178	11⅞	283	807	366	835	379
10	250	72⅝	1845	46⅞	1178	15⅝	397	12⅝	314	27½	699	48	1219	9	229	12⅝	314	1205	547	1243	564

* Indicates nominal dimensions with NRS Gate Valves

** Indicates nominal dimensions with OSY Gate Valves (Full Open Position)

*** Indicates weight of complete Backflow Assemblies with specified Gate Valves


The gap drain is not designed to catch the maximum discharge possible from the relief valve. The installation of the FEBCO air gap with the drain line terminating above a floor drain will handle any normal discharge or nuisance spitting through the relief valve. However, floor drain size may need to be designed to prevent water damage caused by a catastrophic failure condition. Do not reduce the size of the drain line from the air gap fitting.

Performance

Flow capacity chart identifies valve performance based upon rated water Velocity up to 20fps

- Maximum service flow rate is determined by maximum rated Velocity of 7.5fps.
- AWWA Manual M-22 (Appendix C) recommends that the maximum water Velocity in the services be not more than 10fps.
- UL flow rate is determined by typically rated Velocity of 15 feet/sec.

Capacity



A WATTS Brand

USA: Tel: (800) 767-1234 • Fax: (800) 788-4491 • FEBCOonline.com
 Canada: Tel: (905) 332-4090 • Fax: (905) 332-7068 • FEBCOonline.ca
 Latin America: (52) 81-1001-8600 • Fax: (52) 81-8000-7091 • FEBCOonline.com

Application

Ideal for use where Lead-Free* valves are required. Designed for installation on potable water lines to protect against both backsiphonage and backpressure of contaminated water into the potable water supply. Assembly shall provide protection where a potential health hazard exists.



Standards Compliance

- ASSE® Listed 1013
- IAPMO® Listed
- CSA® Certified B64.4
- AWWA Compliant C511
- Approved by the Foundation for Cross Connection Control and Hydraulic Research at the University of Southern California
- Meets the requirements of NSF/ANSI 61*
*(0.25% MAX. WEIGHTED AVERAGE LEAD CONTENT)
- UL® Classified (less shut-off valves or with OS&Y valves)
- C-UL® Classified

Materials

Main valve body	Low Lead Cast Bronze ASTM B 584
Access covers	Low Lead Cast Bronze ASTM B 584
Fasteners	Stainless Steel, 300 Series
Elastomers	Silicone (FDA Approved) Buna Nitrile (FDA Approved)
Polymers	Noryl™
Springs	Stainless Steel, 300 series
Ball valve handles	Stainless Steel

Features

Sizes: 3/4", 1", 1-1/4", 1-1/2", 2"	
Maximum working water pressure	175 PSI
Maximum working water temperature	180°F
Hydrostatic test pressure	350 PSI
End connections Threaded	ANSI B1.20.1

Relief Valve discharge port:

3/4" - 1"	-	0.63 sq. in.
1 1/4" - 2"	-	1.19 sq. in.

Options


(Suffixes can be combined)

- ☐ - with full port QT ball valves (standard)
- ☐ MS - with integral relief valve monitor switch
- ☐ S - with bronze "Y" type strainer
- ☐ BMS - with battery operated monitor switch
- ☐ FT - with integral male 45° flare SAE test fitting
- ☐ TCU - with test cocks up
- ☐ V - with union swivel elbows (3/4" & 1")
- ☐ SE - with street elbows (3/4" & 1")
- ☐ U - with union ball valves
- ☐ PF - with Z-Bite™ push fit connections* (1/2"-1" only)
- ☐ PR - with Z-Press™ press fit connections*

*Fittings ship in box with valve and must be threaded into valve by hand on site.


Accessories

- ☐ Air gap (Model AG)
- ☐ Repair kits (rubber only)
- ☐ Thermal expansion tank (Mdl. XT)
- ☐ Soft seated check valve (Model 40XL2)
- ☐ Shock arrester (Model 1250XL)
- ☐ QT-SET Quick Test Fitting Set
- ☐ Ball valve handle locks
- ☐ Test Cock Lock (Model TCL24)





Dimensions & Weights (do not include pkg.)

MODEL SIZE		DIMENSIONS (approximate)														WITH BALL VALVES	
		A		B		C		D		E		F		G			
		in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	lbs.	kg
3/4	20	12	305	7 3/4	197	2 1/8	54	3	76	3 1/2	89	5	127	16 1/8	410	12	5.5
1	25	13	330	7 3/4	197	2 1/8	54	3	76	3 1/2	89	5	127	17 3/8	441	14	6.4
1 1/4	32	17	432	10 15/16	278	2 3/4	70	3 1/2	89	5	127	6 3/4	171	22 9/16	573	28	12.7
1 1/2	40	17 3/8	441	10 15/16	278	2 3/4	70	3 1/2	89	5	127	6 3/4	171	24 1/16	611	28	12.7
2	50	18 1/2	470	10 15/16	278	2 3/4	70	3 1/2	89	5	127	6 3/4	171	26 1/2	673	34	15.4

MODEL 975XL2 3/4", 1", 1 1/4", 1 1/2" & 2" (STANDARD & METRIC)**Typical Installation**


Local codes shall govern installation requirements. To be installed in accordance with the manufacturers' instructions and the latest edition of the Uniform Plumbing Code. Unless otherwise specified, the assembly shall be mounted at a minimum of 12" (305mm) and a maximum of 30" (762mm) above adequate drains with sufficient side clearance for testing and maintenance. The installation shall be made so that no part of the unit can be submerged.

Capacity thru Schedule 40 Pipe				
Pipe size	5 ft/sec	7.5 ft/sec	10 ft/sec	15 ft/sec
1/8"	1	1	2	3
1/4"	2	2	3	5
3/8"	3	4	6	9
1/2"	5	7	9	14
3/4"	8	12	17	25
1"	13	20	27	40
1 1/4"	23	35	47	70
1 1/2"	32	48	63	95
2"	52	78	105	167

**Specifications**

The Reduced Pressure Principle Backflow Preventer shall be certified to NSF/ANSI 61 shall be ASSE® Listed 1013, rated to 180°F, and supplied with full port ball valves. The main body and access covers shall be low lead bronze (ASTM B 584), the seat ring and all internal polymers shall be Noryl™ and the seat disc elastomers shall be silicone. The first and second checks shall be accessible for maintenance without removing the relief valve or the entire device from the line. If installed indoors, the installation shall be supplied with an air gap adapter and integral monitor switch. The Reduced Pressure Principle Backflow Preventer shall be a ZURN WILKINS Model 975XL2.

INSTALLATION DETAILS



ISSUE DATE 03-28-03

NOT TO SCALE

GRANT & DZURO


Engineers
Surveyors
Planners

1100 Main Street The Villages, FL 32154
Tel No. (352)753-6260 Fax No. (352)753-6264

REVISIONS 4-21-08

5/8"x3/4" & 3/4" COMMERCIAL
WATER METER ASSEMBLY DETAIL

PAGE
W-22



ISSUE DATE 03-28-03

NOT TO SCALE

**GRANT
&
DZURO**


Engineers
Surveyors
Planners

1071 Canal Street The Villages, FL 32162
Tel No. (352)753-6260 Fax No. (352)753-6264

REVISIONS 4-27-05 4-21-08

1" COMMERCIAL WATER METER ASSEMBLY DETAIL

PAGE
W-24



ISSUE DATE 03-28-03

NOT TO SCALE

**GRANT
&
DZURO**


Engineers
Surveyors
Planners

1071 Canal Street The Villages, FL 32162
Tel No. (352)753-6260 Fax No. (352)753-6264

REVISIONS 4-28-05 4-21-08

1-1/2" COMMERCIAL WATER
METER ASSEMBLY DETAIL

PAGE
W-25



ALTERNATE METER BOX
IN NON-PEDESTRIAN AND
NON-VEHICULAR AREAS METER BOX
MAY BE A MID STATES PLASTICS
MSBCF 1324-12

ISSUE DATE 03-28-03


NOT TO SCALE

GRANT & DZURO
Engineers
Surveyors
Planners
1100 Main Street The Villages, FL 32154
Tel No. (352)753-6260 Fax No. (352)753-6264

REVISIONS 8-23-03 4-21-08

**2" COMMERCIAL WATER
METER ASSEMBLY DETAIL**

PAGE
W-26



GRANT & DZURO

Engineers
Surveyors
Planners


1071 Canal Street The Villages, FL 32162
Tel No. (352)753-6260 Fax No. (352)753-6264

REVISIONS 4-27-05 8-9-05 4-21-08

**3" COMMERCIAL WATER
METER ASSEMBLY DETAIL**

PAGE

W-27



NOT TO SCALE

**GRANT
&
DZURO**


Engineers
Surveyors
Planners

1071 Canal Street The Villages, FL 32162
Tel No. (352)753-6260 Fax No. (352)753-6264

REVISIONS	4-27-05	8-9-05	4-21-08			
-----------	---------	--------	---------	--	--	--

4" COMMERCIAL WATER METER ASSEMBLY DETAIL

PAGE
W-28



NOT TO SCALE

**GRANT
&
DZURO**



Engineers
Surveyors
Planners

1071 Canal Street The Villages, FL 32162
Tel No. (352)753-6260 Fax No. (352)753-6264

REVISIONS 4-27-05 8-9-05 4-21-08

**6" COMMERCIAL WATER
METER ASSEMBLY DETAIL**

PAGE
W-29



NOTE: SEE APPROPRIATE ASSEMBLY DETAILS FOR ADDITIONAL INFORMATION

TO BE USED FOR HIGHER RISK FACILITIES ONLY, SUCH AS:

COMMERCIAL CAR WASH
 COMMERCIAL LAUNDRIES / DRY CLEANERS
 PHOTO PROCESSING FACILITIES
 PEST CONTROL COMPANIES
 COOLING TOWERS
 HOSPITALS
 MEDICAL & DENTAL OFFICES
 ASSISTED LIVING/NURSING FACILITIES
 VETERINARY CLINICS
 WASTEWATER LIFT STATIONS (IF SERVED BY POTABLE WATER)
 WASTEWATER TREATMENT PLANT
 MAINTENANCE FACILITY (GOLF, LANDSCAPE, ETC.)
 GROCERY STORE
 BEAUTY SALON/SPA
 HOME IMPROVEMENT/HARDWARE
 FUNERAL HOME
 EYE CARE CLINIC
 LABORATORY / BLOOD CENTER
 AUTOMOTIVE / TIRE STORE

ISSUE DATE 07-11-03

1 OF 2

NOT TO SCALE

GRANT & DZURO
 Engineers
 Surveyors
 Planners
 1071 Canal Street The Villages, FL 32162
 Tel No. (352)753-6260 Fax No. (352)753-6264

REVISIONS

3-27-07


3-23-09

9-15-11

**BACKFLOW PREVENTER
 ASSEMBLY DETAIL**

PAGE

W-51



DISTRIBUTER:
HOTBOX
924 LANE AVE. N.
JACKSONVILLE, FL 32254
(800) 736-0238
(904) 786-0204

NOTE:
ENCLOSURE REQUIRED ONLY IF A RPZ
BACKFLOW PREVENTER MUST BE INSTALLED
ABOVE GRADE IN NON-LANDSCAPED AREAS

ISSUE DATE 03-23-09

2 OF 2

NOT TO SCALE

GRANT & DZURO

Engineers
Surveyors
Planners

1071 Canal Street The Villages, FL 32162
Tel No. (352)753-6260 Fax No. (352)753-6264

REVISIONS

**BACKFLOW PREVENTER
ASSEMBLY DETAIL**

PAGE

W-51